

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180425	Call Order: 020	Proposal: T7415	District:07
Counties:	PINELLAS			
Road Name:	SR 60 AND SR 687			
Limits:	VARIOUS LOCATIONS			
Project(s):	43982935201(*)	Federal Aid No: D717011B		
Total Roadway Length:	5.787 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	04/25/18	
Total Proposal Length:	5.787 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Calendar Days	
Proposal Budget Estimate:	\$580,000.00			

Please read the full advertisement

Description:

The improvements under this contract consist of lighting, sidewalk, curb and gutters, and signing at various locations along SR 60 and SR 687.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 020 Proposal: T7415

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43982935201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43982935201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	36,450.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,550.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	300.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,490.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,500.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	22.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	137.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	22.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	109.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43982935201)	LS	1.000
Section 0002 Signing				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	15.000
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,116.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	31.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	6,219.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,845.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,557.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	4.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	5.000
	0715- 4- 22	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	10.000
	0715- 4- 71	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	15.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	31.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	21.000