

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180829	Call Order: 005	Proposal: T3614	District:03
Counties:	ESCAMBIA			
Road Name:	CRARY RD			
Limits:	OVER PRITCHETT MILL CREEK, BR NO. 484048			
Project(s):	43228815201(*)	Federal Aid No: D318024B		
Total Roadway Length:	0.157 Miles	Contract Days:	120	
Total Bridge Length:	0.004 Miles	Letting Date:	08/29/18	
Total Proposal Length:	0.161 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 days acquis.	

Proposal Budget Estimate: \$854,210.00

Please read the full advertisement

Description:

The improvements under this contract consist of the construction of Bridge Culvert No. 484270 on Crary Road over Pritchett Mill Creek, removal of existing Bridge No. 484048, construction of paved roadway approaches, drainage improvements, an offsite detour, and other incidental construction on Crary Road in Escambia County from County MP 0.765 to County MP 0.926.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 005 Proposal: T3614

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43228815201)	LS	1.000
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	608.000
	0125- 3-	SELECT BEDDING MATERIAL	CY	608.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	173.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	32,117.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	3.400
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	75.200
	0530- 74-	BEDDING STONE	TN	26.800
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43228815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43228815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,320.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,880.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	480.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	720.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,223.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	308.000
	0110- 1- 1	CLEARING & GRUBBING (43228815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,126.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,899.000
	0160- 4-	TYPE B STABILIZATION	SY	3,792.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	5,819.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	2,416.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	216.800
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	47.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	0.900
	0530- 74-	BEDDING STONE	TN	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,819.000
Section 0003 Signing				
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43228815201)	LS	1.000