

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT181205 Call Order: 004 Proposal: T1731 District:01
Counties: MANATEE
Road Name: SR 684 (CORTEZ RD)
Limits: AT VARIOUS INTERSECTIONS AS LISTED IN THE PLANS
Project(s): 44012015201(*) Federal Aid No: D118026B
Project(s): 44012215201 Federal Aid No: D118027B
Total Roadway Length: 14.117 Miles Contract Days: 200
Total Bridge Length: 0.000 Miles Letting Date: 12/05/18
Total Proposal Length: 14.117 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 120 Days (Aqui Time)

Proposal Budget Estimate: \$974,531.00

Please read the full advertisement

Description:

The improvements under this contract consist of lighting at various intersections on State Road 684 (Cortez Road) from Gulf Drive easterly 8.011 miles to 9th Street West and State Road 683 (U.S. 301) from Tallevast Road northerly 6.106 miles to 9th Street East in Manatee County.

Call Order: 004 Proposal: T1731

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44012015201)	LS	1.000
	0101- 1-	MOBILIZATION (44012215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,200.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,712.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	400.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	456.000
	0107- 1-	LITTER REMOVAL	AC	26.630
	0107- 2-	MOWING	AC	23.340
	0110- 1- 1	CLEARING & GRUBBING (44012015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44012215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	43.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	47.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	353.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012215201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,153.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	4,060.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	152.000

Call Order: 004 Proposal: T1731

ALT	Item	Description	Unit	Quantity
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	90.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	23,574.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,137.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	2.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	18.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	19.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	1.000
	0715- 4- 21	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 22	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	5.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	4.000
	0715- 4- 33	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 40' MOUNTING HEIGHT	EA	1.000
	0715- 4- 41	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 42	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	10.000
	0715- 4- 71	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	11.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	44.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	55.000