



**Call Order: 005 Proposal: T1738**

ALT	Item	Description	Unit	Quantity
	0120- 6-	EMBANKMENT	CY	2.300
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	224.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	3,235.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	180.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	205.800
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	2.000
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0425- 6-	VALVE BOXES, ADJUST	EA	8.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	8.000
	0430-175-215	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 15"S/CD	LF	168.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	619.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	821.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	195.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	322.000
	0527- 2-	DETECTABLE WARNINGS	SF	200.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	212.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43837115201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	11.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	11.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	11.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	11.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	6.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	17.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43837115201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.051
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	892.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	12.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,002.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	18.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	16.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.008
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.253
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.030
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.733

**Call Order: 005 Proposal: T1738**

ALT	Item	Description	Unit	Quantity
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	142.000
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	174.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	16.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	6.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	5.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	16.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	10.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	3.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	10.000
	0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	6.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	10.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000