

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT181205 Call Order: 007 Proposal: T2709 District:02
 Counties: TAYLOR
 Road Name: CR 361 (KEATON BEACH RD)
 Limits: OVER CYPRESS CREEK BR AND FISH CREEK BR
 Project(s): 21284435201(*) Federal Aid No: D218015B
 Project(s): 41524815201 Federal Aid No: D218016B
 Total Roadway Length: 0.388 Miles Contract Days: 320
 Total Bridge Length: 0.011 Miles Letting Date: 12/05/18
 Total Proposal Length: 0.399 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Days (Acq. time)
 Proposal Budget Estimate: \$3,198,294.00

Please read the full advertisement

Description:

The improvements under this contract consist of replacing CR 361 over Cypress Creek Bridge No. 380038 from MP 11.630 to MP 11.835 and CR 361 over Fish Creek Bridge No. 380068 from MP 13.318 to MP 13.512. This includes milling and resurfacing, base work, shoulder treatment, drainage improvements, shoulder gutter, highway signing, guardrail, box culvert, temporary critical retaining walls and other incidental construction items in Taylor County.

Call Order: 007 Proposal: T2709

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (21284435201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (41524815201)	LS	1.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	9.800
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	70.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	96.600
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	194.400
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	46.600
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	285.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	3.200
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	46,163.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	17,978.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	6,950.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	19,120.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	240.000
	0455- 35- 22	STEEL PILING, 24" DIA. PIPE	LF	588.000
	0455-120- 7	PILE POINT PROTECTION, 24" ROUND	EA	14.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	3,646.000
	0455-144- 22	TEST PILES - STEEL, 24" DIA PIPE	LF	128.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	82.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	378.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	78.600
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,290.000

Call Order: 007 Proposal: T2709

ALT	Item	Description	Unit	Quantity
	0530- 74-	BEDDING STONE	TN	482.000
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	2,142.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (21284435201)	LS	1.000
	0101- 1-	MOBILIZATION (41524815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21284435201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41524815201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (21284435201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (41524815201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (41524815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	10,000.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	3,282.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	2,014.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,932.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,760.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,236.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	14.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,168.000
	0102-911- 3	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, OTHER	SF	144.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,295.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	500.000
	0110- 1- 1	CLEARING & GRUBBING (21284435201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (41524815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	984.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,566.000
	0120- 4-	SUBSOIL EXCAVATION	CY	328.000
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	946.000
	0125- 3-	SELECT BEDDING MATERIAL	CY	153.000
	0160- 4-	TYPE B STABILIZATION	SY	3,625.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	3,755.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,338.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	2,276.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	359.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	3,619.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	182.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	825.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	59.200
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	8.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	128.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	8.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,830.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	1,573.900
	0530- 74-	BEDDING STONE	TN	1,130.800
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,701.000

Call Order: 007 Proposal: T2709

ALT	Item	Description	Unit	Quantity
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	8.000
	0536- 73-	GUARDRAIL REMOVAL	LF	700.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,755.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.179
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.179
Section 0003 Signing				
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	8.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21284435201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41524815201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.753
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.753
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.045
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.045