

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT181205 Call Order: 008 Proposal: T2723 District:02
 Counties: GILCHRIST
 Road Name: SR 49 (US 129)
 Limits: FROM LEVY CO LINE TO THE END OF CURB AND GUTTER
 Project(s): 43762015201(*) Federal Aid No: D218049B
 Total Roadway Length: 2.758 Miles Contract Days: 120
 Total Bridge Length: 0.000 Miles Letting Date: 12/05/18
 Total Proposal Length: 2.758 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days Acquis.
 Proposal Budget Estimate: \$2,082,761.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, curb and gutter, traffic signals, highway signing, sidewalk, and other incidental construction on SR 49 (US 129) from Levy County line to the end of curb and gutter in Gilchrist County.

Call Order: 008 Proposal: T2723

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43762015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43762015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	80.000
	0102- 60-	WORK ZONE SIGN	ED	8,280.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,720.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	298.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,172.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	240.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	120.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	120.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	120.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	85.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	29.000
	0107- 1-	LITTER REMOVAL	AC	89.110
	0107- 2-	MOWING	AC	62.190
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43762015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43762015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	483.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	150.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,532.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	69.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	3,747.000

Call Order: 008 Proposal: T2723

ALT	Item	Description	Unit	Quantity
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	28,499.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	9,328.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	13,476.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	11,129.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4,528.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	5,469.600
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	6.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	444.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	357.000
	0527- 2-	DETECTABLE WARNINGS	SF	228.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,539.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	15.648
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.624
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	4,011.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	3,726.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,194.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.333
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	21.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	33.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	14.100
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.033
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,872.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.454
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43762015201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	15.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	13.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	6.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	2.291
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.288
	0701- 18-221	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.818
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43762015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,337.000

Call Order: 008 Proposal: T2723

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,242.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	398.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.111
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	11.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	624.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	570.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.925
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.208
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.412
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.011
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	237.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	384.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	8.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	8.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	8.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000