

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT181205 Call Order: 011 Proposal: T3679 District:03  
 Counties: HOLMES  
 Road Name: HICKS RD  
 Limits: OVER WEST PITTMAN CREEK  
 Project(s): 43388415201(\*) Federal Aid No: D318026B  
 Project(s): 43390315201 Federal Aid No: D318028B  
 Total Roadway Length: 0.100 Miles Contract Days: 365  
 Total Bridge Length: 0.027 Miles Letting Date: 12/05/18  
 Total Proposal Length: 0.127 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Days Standard Acq  
 Proposal Budget Estimate: \$2,260,669.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of construction of Bridge No. 524219 on Hicks Road Over West Pittman Creek and removal of existing Bridge No. 524204. Goes with 433903-1-52-01, on Hicks Road Over West Pittman Creek bridge removal of existing Bridge No. 524125 and construction of Bridge No. 524220. Major Items of Work to be performed include roadway, structures, removal of existing Bridge No. 524203 and installation of temporary Acrow Bridge for offsite detour. Other incidental work includes removal of offsite detour, barricades and temporary bridge located on Hicks Road in Holmes County, Florida.

**Call Order: 011 Proposal: T3679**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43388415201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43390315201)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	84.700
	0400- 2- 47	CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	101.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	276.600
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	372.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	6.900
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	24,014.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	45,713.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	16,823.000
	0450- 8- 12	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 52-54"	LF	233.000
	0450- 8- 22	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 15", WIDTH 52-54"	LF	586.000
	0455- 35- 22	STEEL PILING, 24" DIA. PIPE	LF	1,524.000
	0455-144- 22	TEST PILES - STEEL, 24" DIA PIPE	LF	490.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	135.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	446.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	32.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	583.400
	0530- 74-	BEDDING STONE	TN	207.900

**Call Order: 011 Proposal: T3679**

ALT	Item	Description	Unit	Quantity
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	400.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	16.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43388415201)	LS	1.000
	0101- 1-	MOBILIZATION (43390315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43388415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43390315201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43388415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,395.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	168.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	730.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	84.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,161.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	372.000
	0110- 1- 1	CLEARING & GRUBBING (43388415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43390315201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	197.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,834.400
	0160- 4-	TYPE B STABILIZATION	SY	1,429.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	2,285.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,429.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	157.100
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	162.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	10.400
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,285.000
<b>Section 0003 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	8.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43388415201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43390315201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.201
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.201
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.053
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.053