

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT181205 Call Order: 013 Proposal: T3684 District:03
 Counties: WAKULLA
 Road Name: SR 30 (US 98) (Coastal Hwy.)
 Limits: FROM ST. MARKS RIVER TO THE JEFFERSON CO. LINE
 Project(s): 43774815201(*) Federal Aid No: D318053B
 Total Roadway Length: 6.121 Miles Contract Days: 210
 Total Bridge Length: 0.054 Miles Letting Date: 12/05/18
 Total Proposal Length: 6.175 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$6,856,724.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, guardrail, highway signing, and pavement markings along SR 30 (US 98) (Coastal Hwy.).

Call Order: 013 Proposal: T3684

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43774815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43774815201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43774815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,160.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,796.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	2,724.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	179,537.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	840.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	3,114.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	868.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	420.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	683.000
	0104- 10- 3	SEDIMENT BARRIER	LF	30,037.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	258.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	264.560
	0107- 2-	MOWING	AC	227.260
	0110- 1- 1	CLEARING & GRUBBING (43774815201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	12,337.900
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43774815201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	547.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	66,707.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	474.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	91,025.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	2,341.000

Call Order: 013 Proposal: T3684

ALT	Item	Description	Unit	Quantity
	0327- 70- 10	MILLING EXIST ASPH PAVT, 5" AVG DEPTH	SY	417.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	8,972.900
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	13,499.400
	0337- 7- 91	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, HIGH POLYMER	TN	10,308.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	105.900
	0370- 1-	BRIDGE APPROACH EXPANSION JOINT FOR CONCRETE PAVEMENT	LF	47.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	50.600
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	64.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	405.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	243.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	1,017.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	67.400
	0530- 74-	BEDDING STONE	TN	48.400
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,007.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,880.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	4.000
	0570- 1- 1	PERFORMANCE TURF	SY	47,774.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	24,359.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	38.956
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	106.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.020
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.784
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	16.632
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43774815201)	LS	1.000
Section 0002 Signing				
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	10.411
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43774815201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	53.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.510
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	12.438
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.377
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	5.544