

Call Order: 014 Proposal: T3693

ALT	Item	Description	Unit	Quantity
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	3,044.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	72,478.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	1,778.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	922.400
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	4,218.900
	0334- 1- 58	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, HIGH POLYMER	TN	23,886.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	7,843.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	689.900
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	2.900
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	75.000
	0430-612-025	U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 18"PIPE	EA	2.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	69,662.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	4,689.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	4,113.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	2,619.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	2,560.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	10.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	10.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0536- 85- 28	GUARDRAIL END TREATMENT- DOUBLE FACE TRAILING ANCHORAGE	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	26.375
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	82,683.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	225.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	61.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.113
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	26.312
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.113
	0904-540- 13	HIGH TENSION CABLE BARRIER SYSTEM - LENGTH OF NEED SEGMENT	LF	8,193.000
	0904-540- 14	HIGH TENSION CABLE BARRIER SYSTEM - END TERMINAL	EA	6.000
	0904-540- 15	HIGH TENSION CABLE BARRIER SYSTEM, END TERMINAL FOUNDATION- MISCELLANEOUS DRILLED SHAFT	CY	24.000
	0904-540- 16	HIGH TENSION CABLE BARRIER SYSTEM, CONCRETE MOW STRIP	LF	8,193.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43776515201)	LS	1.000
Section 0002 Signing				
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	6.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000

Call Order: 014 Proposal: T3693

ALT	Item	Description	Unit	Quantity
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43776515201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	13.113
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	13.156
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	13.113