

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT181205	Call Order: 021	Proposal: T6457	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 5 (US 1)			
Limits:	SIGNALIZED INTERSECTION LIGHTING			
Project(s):	44018415201(*)	Federal Aid No:	D618043B	
Project(s):	44018515201	Federal Aid No:	D618044B	
Project(s):	44018815201	Federal Aid No:	D618045B	
Total Roadway Length:	21.874 Miles	Contract Days:	240	
Total Bridge Length:	0.000 Miles	Letting Date:	12/05/18	
Total Proposal Length:	21.874 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Calendar Days	
Proposal Budget Estimate:	\$1,906,436.00			

Please read the full advertisement

Description:

The improvements under this contract consists of lighting improvements along SR 5 (US 1).

Call Order: 021 Proposal: T6457

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44018415201)	LS	1.000
	0101- 1-	MOBILIZATION (44018515201)	LS	1.000
	0101- 1-	MOBILIZATION (44018815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44018415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44018515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44018815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	12,290.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	27,605.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	2,420.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	7,860.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,210.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,294.000
	0110- 1- 1	CLEARING & GRUBBING (44018415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	587.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44018415201)	LS	1.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44018515201)	LS	1.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44018815201)	LS	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	581.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44018415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44018515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44018815201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	14,541.000

Call Order: 021 Proposal: T6457

ALT	Item	Description	Unit	Quantity
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	105.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	184.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	52,510.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	20,422.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	22,260.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	25.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	11.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	27.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	1.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	4.000
	0715- 4- 42	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	3.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	2.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	139.000
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	6.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	110.000