

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180228 Call Order: 005 Proposal: T1703 District:01

Counties: GLADES

Road Name: SR 78

Limits: FROM N OF CANAL RD TO S OF KILPATRICK DR

Project(s): 43668315201(*) Federal Aid No: D117108B

Total Roadway Length:	0.078 Miles	Contract Days:	100
Total Bridge Length:	0.000 Miles	Letting Date:	02/28/18
Total Proposal Length:	0.078 Miles	Contract Execution Days:	10
		Special Start Date:	06/05/18
		Aquis/Flexible Start Time:	N/A

Proposal Budget Estimate: \$373,773.00

Please read the full advertisement

Description: Incentive / Disincentive

The improvements under this contract consist of replacing concrete approach slabs adjacent to SCFE Railroad Crossing No. 627662K, milling and resurfacing, base work, shoulder treatment, drainage improvements, guardrail, and pavement markings on State Road 78 north of Canal Road northerly 0.078 miles to south of Kilpatrick Drive in Glades County.

Call Order: 005 Proposal: T1703

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43668315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43668315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,400.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	431.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	431.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,550.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	200.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS	ED	200.000
	0102-911- 3	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, OTHER	SF	48.000
	0104- 10- 3	SEDIMENT BARRIER	LF	521.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	40.000
	0107- 1-	LITTER REMOVAL	AC	2.780
	0107- 2-	MOWING	AC	2.430
	0110- 1- 1	CLEARING & GRUBBING (43668315201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	49.400
	0120- 6-	EMBANKMENT	CY	294.500
	0160- 4-	TYPE B STABILIZATION	SY	870.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	330.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	402.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	231.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	904.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	174.800
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	105.700

Call Order: 005 Proposal: T1703

ALT	Item	Description	Unit	Quantity
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76 -22	TN	105.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	30.800
	0350- 4- 13	REINFORCED CEMENT CONCRETE PAVEMENT,12"	SY	227.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	161.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	14,871.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	74.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	402.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	336.000
	0536- 73-	GUARDRAIL REMOVAL	LF	339.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- FLARED	EA	1.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- TYPE II	EA	1.000
	0536- 85- 26	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	419.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	330.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.151
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.141
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43668315201)	LS	1.000
Section 0002 Signing				
	0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	20.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43668315201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	24.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.151
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.151