

Call Order: 009 Proposal: T3639

ALT	Item	Description	Unit	Quantity
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	21,162.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	79.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	5.700
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-421	INLETS, CURB, TYPE J-2, <10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	4.000
	0425- 6-	VALVE BOXES, ADJUST	EA	4.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	40.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	453.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	311.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	48.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	9.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	13.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	79.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	9.900
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	819.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	422.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	116.000
	0527- 2-	DETECTABLE WARNINGS	SF	47.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,081.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER- BRIDGE ANCHORAGE ASSEMBLY CONNECTION, FURNISH & INSTALL	EA	2.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,007.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- FLARED	EA	6.000
	0546- 71-	RUMBLE STRIPS	PS	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	47,365.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	31.839
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	112.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	376.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.024
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	10.890
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	28.342
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43078915201)	LS	1.000

Call Order: 009 Proposal: T3639

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	29.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	1.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	27.937
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	0.175
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43078915201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	112.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	376.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.024
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.902
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.270
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	14.171
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	3,884.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.809
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.684
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.062