

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180228 Call Order: 012 Proposal: T6453 District:06
 Counties: MIAMI-DADE
 Road Name: SR 7 (NW 7TH AVE)
 Limits: FROM SW 6TH ST TO NW 62ND ST
 Project(s): 44018615201(*) Federal Aid No: D618004B
 Total Roadway Length: 4.496 Miles Contract Days: 120
 Total Bridge Length: 0.000 Miles Letting Date: 02/28/18
 Total Proposal Length: 4.496 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 90 Calendar Days

Proposal Budget Estimate: \$398,145.00

Please read the full advertisement

Description:

The improvements under this contract consists of lighting along SR 7 (NW 7th Ave.).

Call Order: 012 Proposal: T6453

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44018615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44018615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,160.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,920.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	240.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,460.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	268.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	90.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (44018615201)	LS	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	90.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44018615201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,151.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	21.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	4,761.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	3,555.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	6.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	43.000
	0715- 21- 2	LIGHTING REPAIRS AND RETROFITS, LED RETROFIT KIT FOR EXISTING LUMINAIRE (44018615201)	EA	24.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	6.000