

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	CT180131	Call Order: 007	Proposal: T2688	District:02
Counties:	BAKER			
Road Name:	SR 8 (I-10)			
Limits:	AT THE SR 10 (US 90) AND CR 125 INTERCHANGES			
Project(s):	43500115201(*)	Federal Aid No:	D217078B	
Project(s):	43500315201	Federal Aid No:	D217079B	
Total Roadway Length:	0.681 Miles	Contract Days:	180	
Total Bridge Length:	0.042 Miles	Letting Date:	01/31/18	
Total Proposal Length:	0.681 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$1,887,519.00			

Please read the full advertisement

**Description:**

The improvements under this contract consist of the installation of highway lighting and other incidental construction on SR 8 (I-10) at the SR 10 (US 90) and CR 125 interchanges in Baker County.

Railroad insurance is required for this Proposal at time of contract execution. Please see the Specifications Package for more information.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 007 Proposal: T2688**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43500115201)	LS	1.000
	0101- 1-	MOBILIZATION (43500315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43500115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43500315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	10,912.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	57,028.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	26.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,592.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	40.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	40.000
	0104- 10- 3	SEDIMENT BARRIER	LF	525.000
	0107- 1-	LITTER REMOVAL	AC	375.720
	0107- 2-	MOWING	AC	238.360
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.200
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43500115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43500315201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	9,290.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,770.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	710.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	85.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	18.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	28,370.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	35,460.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	280.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	8.000
	0715- 19- 13	HIGH MAST LIGHT POLE, FURNISH AND INSTALL, 120'	EA	21.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	21.000