

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180131 Call Order: 009 Proposal: T3621 District:03  
 Counties: WAKULLA  
 Road Name: SR 30/61 (US 98/COASTAL HWY)  
 Limits: FROM FRANKLIN CO LINE TO BOYKIN RD AND FROM BOYKIN RD TO SR 369 (US 319)  
 Project(s): 43626115201(\*) Federal Aid No: D317066B  
 Project(s): 43626115202 Federal Aid No: D317066B  
 Project(s): 43626125201 Federal Aid No: D317067B  
 Total Roadway Length: 13.907 Miles Contract Days: 240  
 Total Bridge Length: 0.051 Miles Letting Date: 01/31/18  
 Total Proposal Length: 13.958 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Days Standard Acq  
 Proposal Budget Estimate: \$7,717,384.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of FPID 436261-1-52-01 and 436261-1-52-02: milling and resurfacing, shoulder reconstruction, sidewalk, curb and gutter, guardrail, drainage improvements, and signing and pavement marking on State Road 30/State Road 61 (US 98/Coastal Highway) from the Ochlockonee Bay Bridge northerly 7.221 miles to Boykin Road and FPID 436261-2-52-01: milling and resurfacing, widening, sidewalk, curb and gutter, guardrail, drainage improvements, signing and pavement marking, and signalization on State Road 30/State Road 61 (US 98/Coastal Highway, US 319/Crawfordville Highway) from Boykin Road northerly 7.327 miles to State Road 369 (US 319/Shadeville Road) in Wakulla County.

**Call Order: 009 Proposal: T3621**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43626115201)	LS	1.000
	0101- 1-	MOBILIZATION (43626115202)	LS	1.000
	0101- 1-	MOBILIZATION (43626125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43626115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43626115202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43626125201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	130.400
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	23,115.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	38,620.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	5,208.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	974.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	290.000
	0104- 10- 3	SEDIMENT BARRIER	LF	10,799.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	60.000

**Call Order: 009 Proposal: T3621**

ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	1,371.950
	0107- 2-	MOWING	AC	1,153.750
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43626115201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43626125201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43626115201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43626125201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43626115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43626115202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43626125201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	330.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	16.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	2,655.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43626115201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43626115202)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43626125201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	7,096.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	12,228.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	3,386.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	486.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	10,313.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,046.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	192,544.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	3,036.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	8,876.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	2,694.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	1,247.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	20,187.300
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	19,547.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	37.600
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	3.300
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	6.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	261.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	4.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	3.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000

**Call Order: 009 Proposal: T3621**

ALT	Item	Description	Unit	Quantity
	0425- 6-	VALVE BOXES, ADJUST	EA	3.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	667.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	109.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	18.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	9.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	2.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	583.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	15.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	219.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	187.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,263.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	557.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	584.000
	0527- 2-	DETECTABLE WARNINGS	SF	374.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	12.000
	0530- 74-	BEDDING STONE	TN	8.700
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	427.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER- BRIDGE ANCHORAGE ASSEMBLY CONNECTION, FURNISH & INSTALL	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	279.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- FLARED	EA	1.000
	0536- 85- 24	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- PARALLEL	EA	1.000
	0538- 1-	GUARDRAIL RESET	LF	591.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	46,456.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	34.319
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.368
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	677.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	402.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,131.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.390
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	38.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	22.910
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	455.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	13.536

**Call Order: 009 Proposal: T3621**

ALT	Item	Description	Unit	Quantity
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.094
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	11.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43626115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43626115202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43626125201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	62.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	8.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870, UP TO 12 SF	AS	3.000
	0700- 1- 40	SINGLE POST SIGN, INSTALL	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	11.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	60.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	4.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	9.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	7.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	13.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	6.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	2.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	15.964
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43626115201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43626125201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	425.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	402.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	792.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.390
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	38.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	455.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.094
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	362.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	738.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	29.000

**Call Order: 009 Proposal: T3621**

ALT	Item	Description	Unit	Quantity
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	25.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	15.354
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.269
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	14.113
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	8.621
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	811.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.234
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.061
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	54.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	222.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	4.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	3.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000