

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180131 Call Order: 010 Proposal: T3662 District:03
 Counties: ESCAMBIA
 Road Name: SR 30/298 (US 98) (LILLIAN HWY)
 Limits: FROM PERDIDO BAY BR TO CR 297 (DOG TRACK RD)
 Project(s): 43627215201(*) Federal Aid No: D317071B
 Project(s): 43627215202 Federal Aid No: N/A
 Total Roadway Length: 3.233 Miles Contract Days: 120
 Total Bridge Length: 0.038 Miles Letting Date: 01/31/18
 Total Proposal Length: 3.271 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 days Acquis.
 Proposal Budget Estimate: \$2,005,750.00

Please read the full advertisement

Description:

The improvements under this contract consist of FPID # 436272-1-52-01 on SR 30/298 (US 98) Lillian Highway from Perdido Bay Bridge to CR 297 Dog Track Road in Escambia County Florida, consist of mill/resurface, guardrail, sidewalks, signing and pavement markings, and traffic signal. FPID 436272-1-52-02 is for Utility Work by Highway Contractor (UWHC) to adjust Valve boxes.

Call Order: 010 Proposal: T3662

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43627215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43627215201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	43.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	112.000
	0102- 60-	WORK ZONE SIGN	ED	5,088.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	13,144.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	10.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,384.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	494.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	240.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,647.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	72.480
	0107- 2-	MOWING	AC	52.070
	0110- 1- 1	CLEARING & GRUBBING (43627215201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	19.000
	0120- 1-	REGULAR EXCAVATION	CY	598.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	289.300
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	1,120.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	1,476.000

Call Order: 010 Proposal: T3662

ALT	Item	Description	Unit	Quantity
	0286- 1-	TURNOUT CONSTRUCTION	SY	218.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	55,413.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	19,802.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	4,249.500
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	5,261.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	15.100
	0425- 6-	VALVE BOXES, ADJUST	EA	6.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	69.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	179.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER- BRIDGE ANCHORAGE ASSEMBLY CONNECTION, FURNISH & INSTALL	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	125.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- FLARED	EA	1.000
	0536- 85- 26	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	11,901.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.686
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.016
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	74.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	529.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.059
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	38.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.658
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,418.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.129
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43627215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43627215202)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	4.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43627215201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	74.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	519.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.037
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	36.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,394.000

Call Order: 010 Proposal: T3662

ALT	Item	Description	Unit	Quantity
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.740
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.029
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.641
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.130
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	607.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.051
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.092
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	78.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	293.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0650- 1- 38	TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 5 SECTION STRAIGHT, 1 WAY	AS	1.000
	0650- 1- 60	TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	7.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000