

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180131 Call Order: 011 Proposal: T3667 District:03  
 Counties: WASHINGTON  
 Road Name: SR 8 (I-10)  
 Limits: FROM THE HOLMES CO LINE (MP 12.906) TO E OF SR 77 (MP 17.409)  
 Project(s): 43273835201(\*) Federal Aid No: D317135B  
 Total Roadway Length: 6.217 Miles Contract Days: 325  
 Total Bridge Length: 0.040 Miles Letting Date: 01/31/18  
 Total Proposal Length: 6.257 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$11,324,711.00

Please read the full advertisement

**Description:**

The improvements under this contract consist of milling and resurfacing of the SR 8 (I-10) travel lanes and shoulders. Milling and resurfacing work includes the four ramps serving the interchange of SR 8 (I-10) at SR 77. Other improvements include ramp shoulder widening, replacement of the edgedrain system, guardrail construction, replacement of ditch pavement, installation of wildlife fencing, signing and pavement markings, and construction of a high tension cable barrier system in the median.

**Call Order: 011 Proposal: T3667**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43273835201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43273835201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43273835201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,150.000
	0102- 60-	WORK ZONE SIGN	ED	13,266.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	1,113.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	89,582.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	273.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,121.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,300.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	738.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	738.000
	0104- 10- 3	SEDIMENT BARRIER	LF	11,665.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	24.000
	0107- 1-	LITTER REMOVAL	AC	1,342.400
	0107- 2-	MOWING	AC	1,127.360
	0110- 1- 1	CLEARING & GRUBBING (43273835201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	7,722.000
	0120- 1-	REGULAR EXCAVATION	CY	413.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,279.000
	0160- 4-	TYPE B STABILIZATION	SY	4,074.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	6,162.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	3,325.000

**Call Order: 011 Proposal: T3667**

ALT	Item	Description	Unit	Quantity
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	28,068.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	60.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	113.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	2,017.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	141,853.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	45,377.000
	0327- 70- 18	MILLING EXIST ASPH PAVT, 5 1/2" AVG DEPTH	SY	2,273.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	83.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	1,122.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	4,231.600
	0334- 1- 58	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, HIGH POLYMER	TN	26,595.200
	0337- 7- 26	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER	TN	5,776.200
	0337- 7- 94	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, HIGH POLYMER	TN	1,483.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	434.400
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	2,273.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	2.000
	0425- 1-505	INLETS, DT BOT, TYPE A, PARTIAL	EA	5.000
	0425- 1-515	INLETS, DT BOT, TYPE B, PARTIAL	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0431- 1- 1	PIPE LINER, OPTIONAL MATERIAL, 0-24"	LF	116.000
	0431- 1- 2	PIPE LINER, OPTIONAL MATERIAL, 25-36"	LF	208.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	49,858.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	6,334.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	7,479.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,557.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	2,578.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	2,578.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,227.000
	0536- 85- 24	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT-PARALLEL	EA	4.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- TYPE II	EA	6.000
	0536- 85- 27	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT-DOUBLE FACE TERMINAL	EA	1.000
	0546- 72- 55	RUMBLE STRIPS, GROUND-IN, 16" SHOULDER	GM	19.500
	0550- 10-149	FENCING, TYPE A, 7.1-8.0', SPECIAL FEATURES	LF	2,847.000
	0570- 1- 1	PERFORMANCE TURF	SY	6,162.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	55,649.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.373
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.820
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	222.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	16.035

**Call Order: 011 Proposal: T3667**

ALT	Item	Description	Unit	Quantity
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	17.829
	0904-540- 13	HIGH TENSION CABLE BARRIER SYSTEM - LENGTH OF NEED SEGMENT	LF	19,500.000
	0904-540- 14	HIGH TENSION CABLE BARRIER SYSTEM - END TERMINAL	EA	10.000
	0904-540- 15	HIGH TENSION CABLE BARRIER SYSTEM, END TERMINAL FOUNDATION- MISCELLANEOUS DRILLED SHAFT	CY	40.000
	0904-540- 16	HIGH TENSION CABLE BARRIER SYSTEM, CONCRETE MOW STRIP	LF	19,450.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43273835201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	24.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	4.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	113.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43273835201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.825
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	112.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	20.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	32.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	9.021
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	8.968
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	9.022
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.876
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.303
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.838
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	532.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.089
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.089
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.089
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.089

Call Order: 011 Proposal: T3667

ALT	Item	Description	Unit	Quantity
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,222.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	214.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	6,192.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	6,100.000