

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180131 Call Order: 012 Proposal: T4470 District:04
 Counties: BROWARD
 Road Name: JOHNSON ST (HOLLYWOOD BLVD)
 Limits: HOLLYWOOD GARDENS SIDEWALK PROJECT
 Project(s): 43467915201(*) Federal Aid No: D417027B
 Project(s): 43467915202 Federal Aid No: D417027B
 Total Roadway Length: 7.277 Miles Contract Days: 337
 Total Bridge Length: 0.000 Miles Letting Date: 01/31/18
 Total Proposal Length: 7.277 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Calendar Days
 Proposal Budget Estimate: \$2,916,745.00

Please read the full advertisement

Description:

The improvements under this contract consist of widening, sidewalks, pavers, driveways, curb and gutters, drainage improvements, fencing, signing and pavement marking, bike lanes, shared road pavement markings and lighting on multiple streets within the Hollywood Gardens Beach area which is bound by Johnson St. (Hollywood Blvd.).

Call Order: 012 Proposal: T4470

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43467915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43467915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,472.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	222.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE, CONCRETE	LF	2,134.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	58,711.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,348.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	3,140.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	568.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	84.000
	0104- 10- 3	SEDIMENT BARRIER	LF	53,822.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	29.000
	0110- 1- 1	CLEARING & GRUBBING (43467915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	6,528.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	72.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43467915201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	472.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	472.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	82.800
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	19.000
	0425- 1-565	INLETS, DITCH BOTTOM, TYPE F, PARTIAL	EA	4.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	43.000

Call Order: 012 Proposal: T4470

ALT	Item	Description	Unit	Quantity
	0443- 70- 4	FRENCH DRAIN, 24"	LF	1,270.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	65.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	24,357.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	49.000
	0527- 2-	DETECTABLE WARNINGS	SF	2,947.000
	0550- 10-218	FENCING, TYPE B, 0.0-5.0', RESET EXISTING	LF	1,077.000
	0550- 10-420	FENCING, WOOD FENCE, 5.1-6.0'	LF	73.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	29,267.000
	0999- 16-	PARTNERING, DO NOT BID (43467915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43467915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43467915202)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	199.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	71.000
	0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	11,363.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,452.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,083.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	48.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.264
	0711- 11-143	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE, 12" FOR ROUNDABOUT	GM	0.113
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	19.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	158.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	820.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,429.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	962.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	32.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.789
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	4.392
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.496
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.061
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	90.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	10,231.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	6,620.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	2.000

Call Order: 012 Proposal: T4470

ALT	Item	Description	Unit	Quantity
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	4.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	8.000
	0715-540-000	LIGHT POLE COMPLETE- SPECIAL DESIGN, RELOCATE	EA	2.000