

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180131 Call Order: 013 Proposal: T4474 District:04
Counties: PALM BEACH
Road Name: CR 798 (PALMETTO PARK RD)
Limits: FROM SR 7 TO NW 2ND AVE
Project(s): 43516015201(*) Federal Aid No: D417111B
Total Roadway Length: 6.147 Miles Contract Days: 294
Total Bridge Length: 0.132 Miles Letting Date: 01/31/18
Total Proposal Length: 6.279 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$3,480,994.00

Please read the full advertisement

Description:

The improvements under this contract consist of construction of a shared use path, minor milling and resurfacing, gravity walls and end wall, guardrail, curb and gutter, sidewalks, detectable warnings, fencing, and signing and pavement markings, along CR798 (Palmetto Park Rd.).

Call Order: 013 Proposal: T4474

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43516015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43516015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,860.000
	0104- 10- 3	SEDIMENT BARRIER	LF	32,340.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,882.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	85.000
	0110- 1- 1	CLEARING & GRUBBING (43516015201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.350
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,246.000
	0120- 1-	REGULAR EXCAVATION	CY	1,624.900
	0120- 6-	EMBANKMENT	CY	1,060.500
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	36,288.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,965.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	2,049.800
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	17.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	179.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	28.300
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	1,471.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	4.500
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	6.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	5.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	348.000

Call Order: 013 Proposal: T4474

ALT	Item	Description	Unit	Quantity
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	12.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	10.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	5,058.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	948.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	16.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	3,142.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,493.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	19.000
	0536- 73-	GUARDRAIL REMOVAL	LF	203.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- TYPE II	EA	1.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	850.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	43,657.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43516015201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	66.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,277.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	202.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	36.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	0.030
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	29.000