

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180725	Call Order: 003	Proposal: T1718	District:01
Counties:	SARASOTA			
Road Name:	SR 72 (CLARK RD)			
Limits:	AT VARIOUS LOCATIONS AS LISTED IN THE PLANS			
Project(s):	44011815201(*)	Federal Aid No: D117091B		
Total Roadway Length:	4.340 Miles	Contract Days:	135	
Total Bridge Length:	0.000 Miles	Letting Date:	07/25/18	
Total Proposal Length:	4.340 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days (Aqui Time)	
Proposal Budget Estimate:	\$508,554.00			

Please read the full advertisement

Description:

The improvements under this contract consist of highway lighting and sidewalks on State Road 72 (Clark Rd.) and the intersections of Sarasota Pavilion Entrance, Gateway Ave., Swift Rd., Lockwood Ridge Rd., Beneva Rd., Sawyer Rd., McIntosh Rd. S., McIntosh Rd. N., Honore Ave., Gantt Rd., and Frontage Rd. in Sarasota County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: T1718

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44011815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44011815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,354.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,013.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	565.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	132.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	29.000
	0107- 1-	LITTER REMOVAL	AC	5.570
	0107- 2-	MOWING	AC	2.600
	0110- 1- 1	CLEARING & GRUBBING (44011815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	162.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	67.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	4.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	115.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44011815201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	290.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,955.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	46.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	15,657.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	78.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	17.000
	0715- 4- 22	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	7.000
	0715- 4- 41	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	3.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	4.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	20.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	31.000