

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT180725	Call Order: 009	Proposal: T3622	District:03
Counties:	WAKULLA			
Road Name:	CR 375			
Limits:	OVER SMITH CREEK			
Project(s):	43403415201(*)	Federal Aid No: D318031B		
Total Roadway Length:	0.284 Miles	Contract Days:	245	
Total Bridge Length:	0.023 Miles	Letting Date:	07/25/18	
Total Proposal Length:	0.307 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Calendar Days	

Proposal Budget Estimate: \$1,966,858.00

Please read the full advertisement

Description:

The improvements under this contract consist of constructing Bridge No. 594067 over Smith Creek, removal of the existing bridge, guardrail upgrades, signing and pavement markings and reconstruction of the bridge approaches on CR 375.

Call Order: 009 Proposal: T3622

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43403415201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	121.800
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	67.200
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	83.000
	0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER	SY	469.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	4.200
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	29,045.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	7,789.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	16,356.000
	0450- 1- 1	PRESTRESSED BEAMS, TYPE II	LF	600.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	520.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	160.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	72.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	360.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	21.200
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	719.900
	0530- 74-	BEDDING STONE	TN	256.400
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43403415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43403415201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43403415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	6.900
	0102- 60-	WORK ZONE SIGN	ED	6,253.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	1,744.000

Call Order: 009 Proposal: T3622

ALT	Item	Description	Unit	Quantity
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,800.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,620.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	270.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	80.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	540.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	11.000
	0104- 10- 3	SEDIMENT BARRIER	LF	8,518.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	504.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	700.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43403415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43403415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43403415201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,145.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	5,127.000
	0160- 4-	TYPE B STABILIZATION	SY	4,326.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	12,359.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	2,980.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	193.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	1,541.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	397.500
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	364.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	39.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	6.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	56.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	276.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	4.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,106.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	11.600
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,138.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER CONNECTION, FURNISH & INSTALL	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	141.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	15,126.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.230
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.230
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43403415201)	LS	1.000
Section 0003 Signing				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000

Call Order: 009 Proposal: T3622

ALT	Item	Description	Unit	Quantity
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43403415201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.568
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.568
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.045
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.045