

Call Order: 010 Proposal: T3633

ALT	Item	Description	Unit	Quantity
	0285-730-	OPTIONAL BASE- GRADED AGGREGATE, 16" FOR PROJECT 431883-3-52-01	SY	2,721.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	649.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	112.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	518.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	97.600
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	2.000
	0425- 1-473	INLETS, CURB, TYPE 7, J BOT , <10'	EA	1.000
	0425- 1-475	INLETS, CURB, TYPE 7, PARTIAL	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	111.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	462.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,368.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	202.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	52.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	7.000
	0527- 2-	DETECTABLE WARNINGS	SF	37.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,403.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43188335201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	11.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	6.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	1.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43188335201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	217.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	70.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.069
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	15.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.447
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.420
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	309.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	278.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	2.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000

Call Order: 010 Proposal: T3633

ALT	Item	Description	Unit	Quantity
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	3.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000