

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180725	Call Order: 016	Proposal: T6462	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 9 (NW 27TH AVE)			
Limits:	FROM NW 23RD ST TO NW 26TH ST			
Project(s):	43792215201(*)	Federal Aid No:	D618037B	
Total Roadway Length:	0.153 Miles	Contract Days:	160	
Total Bridge Length:	0.000 Miles	Letting Date:	07/25/18	
Total Proposal Length:	0.153 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Calendar Days	

Proposal Budget Estimate: \$736,819.00

Please read the full advertisement

Description:

The improvements under this contract consist of safety improvements on SR 9 (NW 27th Ave.).

Call Order: 016 Proposal: T6462

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43792215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43792215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	64.000
	0102- 60-	WORK ZONE SIGN	ED	5,280.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,480.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	400.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	70.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	320.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	348.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	3.190
	0107- 2-	MOWING	AC	0.390
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43792215201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43792215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43792215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	342.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43792215201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43792215201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	290.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	46.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	290.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	3,665.000
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	39.800

Call Order: 016 Proposal: T6462

ALT	Item	Description	Unit	Quantity
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	TN	317.900
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	81.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	333.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	220.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	55.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	143.000
	0527- 2-	DETECTABLE WARNINGS	SF	69.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	46.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.073
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43792215201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43792215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	804.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	20.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	123.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.048
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	5.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	133.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	675.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.209
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.022
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.160
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.302
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	300.000
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	432.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,296.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	3.000

Call Order: 016 Proposal: T6462

ALT	Item	Description	Unit	Quantity
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	5.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,095.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	29.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	311.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	5.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 12	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-40'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	8.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-120	TRAFFIC CONTROLLER ASSEMBLY, F&I, 170	AS	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000