

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180613 Call Order: 012 Proposal: T1707 District:01

Counties: POLK

Road Name: SR 60, SR 548, SR 655 AND SR 540

Limits: AT VARIOUS LOCATIONS AS LISTED IN THE PLANS

Project(s): 44012115201 Federal Aid No: D117092B

Project(s): 44012515201 Federal Aid No: D117100B

Project(s): 44013515201 Federal Aid No: D117096B

Project(s): 44013815201(*) Federal Aid No: D117098B

Total Roadway Length:	8.877 Miles	Contract Days:	125
Total Bridge Length:	0.000 Miles	Letting Date:	06/13/18
Total Proposal Length:	8.877 Miles	Contract Execution Days:	10
		Special Start Date:	01/02/19
		Aquis/Flexible Start Time:	N/A

Proposal Budget Estimate: \$555,696.00

Please read the full advertisement

Description:

The improvements under this contract consist of lighting and sidewalks on State Road 60 from Prairie Mine Road easterly to Crown Avenue, lighting at the intersection of State Road 548 (U.S. 98) and Massachusetts Avenue, lighting on State Road 655 (Recker Hwy.) from Coleman Road westerly to Spirit Lake Road, and lighting at the intersection of State Road 540 (Winterlake Rd.) and Reynolds Road in Polk County.

Call Order: 012 Proposal: T1707

ALT	Item	Description	Unit	Quantity
Section 0001 Lighting				
	0101- 1-	MOBILIZATION (44012115201)	LS	1.000
	0101- 1-	MOBILIZATION (44012515201)	LS	1.000
	0101- 1-	MOBILIZATION (44013515201)	LS	1.000
	0101- 1-	MOBILIZATION (44013815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44013515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44013815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,650.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	330.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	90.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	392.000
	0107- 1-	LITTER REMOVAL	AC	1.320
	0107- 2-	MOWING	AC	0.930
	0110- 1- 1	CLEARING & GRUBBING (44012115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44012515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44013515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44013815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	19.000

Call Order: 012 Proposal: T1707

ALT	Item	Description	Unit	Quantity
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	24.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	113.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	831.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,554.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	55.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	5.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	67.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	8,559.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	405.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	3.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	8.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	4.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	2.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	3.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 33	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 40' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715- 4- 71	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	2.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	5.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	9.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	24.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44013515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44013815201)	LS	1.000