

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180613 Call Order: 015 Proposal: T1715 District:01  
 Counties: OKEECHOBEE  
 Road Name: SR 700  
 Limits: ALONG NW 6TH ST FROM SR 700 TO NW 12TH AVE  
 Project(s): 43902715201(\*) Federal Aid No: D117012B  
 Total Roadway Length: 0.102 Miles Contract Days: 125  
 Total Bridge Length: 0.000 Miles Letting Date: 06/13/18  
 Total Proposal Length: 0.102 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 60 Days (Aqui Time)

Proposal Budget Estimate: \$1,079,420.00

Please read the full advertisement

Description:

The improvements under this contract consist of drainage improvements earthwork, shoulder treatment, asphalt pavement and pavement markings along NW 6th Street from SR 700 to NW 12th Avenue in Okeechobee County.

**Call Order: 015 Proposal: T1715**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43902715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43902715201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43902715201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	49.600
	0102- 60-	WORK ZONE SIGN	ED	3,206.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,338.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	233.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	246.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,702.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	34.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0107- 1-	LITTER REMOVAL	AC	4.090
	0107- 2-	MOWING	AC	3.960
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43902715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43902715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	47.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	7.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43902715201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	20,401.600
	0120- 6-	EMBANKMENT	CY	821.500
	0160- 4-	TYPE B STABILIZATION	SY	753.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	182.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	443.000

**Call Order: 015 Proposal: T1715**

ALT	Item	Description	Unit	Quantity
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	85.200
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	24.300
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	10.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	4.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	148.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,175.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	38.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	1.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	47.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	31.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,149.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43902715201)	LS	1.000
<b>Section 0002 Signing</b>				
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43902715201)	LS	1.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	33.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.010
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.040