

Call Order: 019 Proposal: T2710

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|-----------|
| | 0455-133- 3 | SHEET PILING STEEL, F&I PERMANENT | SF | 5,247.000 |
| | 0455-144- 6 | TEST PILES - STEEL, HP 14 x 89 | LF | 162.000 |
| | 0458- 1- 11 | BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD | LF | 86.000 |
| | 0521- 5- 31 | CONCRETE TRAFFIC RAILING- BRIDGE, 32" SPECIAL DESIGN FOR PROJECT 409267-1-52-01 | LF | 185.000 |
| | 0521- 6- 12 | CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 42" HEIGHT | LF | 93.000 |
| | 0524- 2- 2 | CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4" | SY | 19.000 |
| | 0530- 3- 3 | RIPRAP- RUBBLE, BANK AND SHORE | TN | 231.700 |
| | 0530- 74- | BEDDING STONE | TN | 82.500 |
| Section 0002 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (40926715201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (40926715201) | LS | 1.000 |
| | 0102- 2- 1 | SPECIAL DETOUR 1 (40926715201) | LS | 1.000 |
| | 0102- 3- | COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE | CY | 12.400 |
| | 0102- 60- | WORK ZONE SIGN | ED | 7,685.000 |
| | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE | LF | 240.000 |
| | 0102- 71- 14 | TEMPORARY BARRIER, F&I, TYPE K | LF | 301.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 5,220.000 |
| | 0102- 74- 2 | CHANNELIZING DEVICE, TYPE III, 6' | ED | 1,770.000 |
| | 0102- 74- 7 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | LF | 136.000 |
| | 0102- 78- | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER | EA | 406.000 |
| | 0102- 89- 1 | TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION | LO | 4.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 160.000 |
| | 0104- 1- | ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS | SY | 15.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 736.000 |
| | 0104- 11- | FLOATING TURBIDITY BARRIER | LF | 283.000 |
| | 0104- 12- | STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC | LF | 93.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 2.000 |
| | 0108- 1- | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (40926715201) | LS | 1.000 |
| | 0108- 2- | MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (40926715201) | LS | 1.000 |
| | 0110- 1- 1 | CLEARING & GRUBBING (40926715201) | LS | 1.000 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 171.000 |
| | 0110- 7- 1 | MAILBOX, F&I SINGLE | EA | 2.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 178.000 |
| | 0120- 4- | SUBSOIL EXCAVATION | CY | 52.000 |
| | 0120- 5- | CHANNEL EXCAVATION | CY | 139.000 |
| | 0120- 6- | EMBANKMENT | CY | 576.000 |
| | 0125- 1- | EXCAVATION FOR STRUCTURES | CY | 145.000 |
| | 0160- 4- | TYPE B STABILIZATION | SY | 1,901.000 |
| | 0285-703- | OPTIONAL BASE, BASE GROUP 03 | SY | 1,836.000 |
| | 0334- 1- 12 | SUPERPAVE ASPHALTIC CONC, TRAFFIC B | TN | 108.200 |

Call Order: 019 Proposal: T2710

| ALT | Item | Description | Unit | Quantity |
|-------------------------------|--------------|---|------|-----------|
| | 0337- 7- 81 | ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22 | TN | 133.200 |
| | 0339- 1- | MISCELLANEOUS ASPHALT PAVEMENT | TN | 4.600 |
| | 0400- 1- 2 | CONCRETE CLASS I, ENDWALLS | CY | 2.200 |
| | 0425- 2- 91 | MANHOLES, J-8, <10' | EA | 2.000 |
| | 0430-175-124 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD | LF | 105.000 |
| | 0515- 2-311 | PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1 | LF | 25.000 |
| | 0520- 6- | SHOULDER GUTTER- CONCRETE | LF | 154.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 175.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 92.000 |
| | 0527- 2- | DETECTABLE WARNINGS | SF | 34.000 |
| | 0536- 1- 1 | GUARDRAIL -ROADWAY, GENERAL TL-3 | LF | 144.000 |
| | 0536- 6- | PIPE RAIL FOR GUARDRAIL | LF | 24.000 |
| | 0536- 85- 22 | GUARDRAIL END TREATMENT- FLARED APPROACH TERMINAL | EA | 1.000 |
| | 0536- 85- 26 | GUARDRAIL END TREATMENT- TYPE CRT | EA | 1.000 |
| | 0550- 10-218 | FENCING, TYPE B, 0.0-5.0', RESET EXISTING | LF | 57.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 1,545.000 |
| | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" | GM | 0.367 |
| | 0710- 11-123 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12" | LF | 59.000 |
| | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24" | LF | 37.000 |
| | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" | GM | 0.729 |
| Section 0003 Signing | | | | |
| | 0700- 1- 50 | SINGLE POST SIGN, RELOCATE | AS | 2.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 2.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (40926715201) | LS | 1.000 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 76.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 34.000 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 0.146 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 0.169 |
| | 0713-103-101 | PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES | GM | 0.020 |
| | 0713-103-201 | PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES | GM | 0.020 |
| Section 0004 Utilities | | | | |
| | 1000- 5- | UTILITY WORK- JPA/UTILITY AGREEMENT, SEWER (40926715601) | LS | 1.000 |
| | 1000- 6- | UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (40926715601) | LS | 1.000 |