

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: CT180613 Call Order: 006 Proposal: T7402 District:07  
 Counties: HILLSBOROUGH  
 Road Name: CR 580 (SAM ALLEN RD)  
 Limits: FROM W OF SR 39 (PAUL BUCHMAN HWY) TO E OF PARK RD  
 Project(s): 25786235201(\*) Federal Aid No: 4047203C  
 Project(s): 25786235601 Federal Aid No: N/A  
 Total Roadway Length: 2.018 Miles Contract Days: 760  
 Total Bridge Length: 0.000 Miles Letting Date: 06/13/18  
 Total Proposal Length: 2.018 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Calendar Days  
 Proposal Budget Estimate: \$27,342,724.00

Please read the full advertisement

**Description:**

Railroad insurance is required for this Proposal at time of contract execution. Please see the Specifications Package for more information.

The improvements under this contract consist of widening a two-mile segment of CR 580 (Sam Allen Rd.) by reconstructing the existing two-lane, undivided rural highway into a four-lane, divided urban section with curb and gutter. The Project work includes new pavement, milling and resurfacing, pavement widening, curb and gutter, closed drainage system, ponds and flood plain compensation sites, sidewalks, signing and pavement markings, signals and UWHCA with the City of Plant City.

**Call Order: 006 Proposal: T7402**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (25786235201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (25786235201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (25786235201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (25786235201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	279.600
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	260.000
	0102- 60-	WORK ZONE SIGN	ED	108,336.000
	0102- 61-	BUSINESS SIGN	EA	2.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	14,573.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	418.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	14,175.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	421,004.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	120,473.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,255.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	343.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	7,441.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,320.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	760.000

**Call Order: 006 Proposal: T7402**

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	760.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	1,490.000
	0104- 10- 3	SEDIMENT BARRIER	LF	29,930.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	335.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	6,312.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	7.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	120.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (25786235201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (25786235201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,043.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	27.000
	0120- 1-	REGULAR EXCAVATION	CY	123,327.300
	0120- 4-	SUBSOIL EXCAVATION	CY	23,465.000
	0120- 6-	EMBANKMENT	CY	80,374.500
	0160- 4-	TYPE B STABILIZATION	SY	95,841.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	242.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,538.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	1,028.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	1,896.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	77,222.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	1,882.000
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	110.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	69.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	8,131.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	1,407.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	3,899.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	13,158.400
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	204.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	7,564.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	24.900
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	3,979.600
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	61.100
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	247.800
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	36.700
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	41,013.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	3,674.000
	0425- 1-211	INLETS, CURB, TYPE 10, <10'	EA	4.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	30.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	2.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	24.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	7.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	18.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	3.000

**Call Order: 006 Proposal: T7402**

ALT	Item	Description	Unit	Quantity
	0425- 1-462	INLETS, CURB, TYPE J-6, >10'	EA	11.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	8.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	6.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	1.000
	0425- 1-559	INLETS, DT BOT, TYPE E, MODIFY	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	2.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	20.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	4.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	111.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	226.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	92.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	34.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	50.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	46.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	4,726.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	5,474.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,487.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,917.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	3,497.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	942.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	661.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	748.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/C	LF	164.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	355.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	5.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	1.000
	0430-982-143	MITERED END SECTION, OPTIONAL ROUND, 60" CD	EA	2.000
	0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 30" CD	EA	1.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	6.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	14.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	6.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	4.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	23,541.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	7,752.000
	0515- 2-211	PEDESTRIAN / BICYCLE RAILING, STEEL, 42" TYPE 1	LF	274.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	13,404.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	18,383.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	353.000

**Call Order: 006 Proposal: T7402**

ALT	Item	Description	Unit	Quantity
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	1,896.000
	0520- 5- 16	TRAFFIC SEPARATOR CONCRETE- TYPE I, 8.5' WIDE	LF	266.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	384.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	3.000
	0521- 8- 4	CONCRETE TRAFFIC RAILING BARRIER, WITH JUNCTION SLAB, 42" VERTICAL FACE	LF	147.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	10,705.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,207.000
	0527- 2-	DETECTABLE WARNINGS	SF	561.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	34.800
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	16,860.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	665.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	665.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	16.000
	0536- 73-	GUARDRAIL REMOVAL	LF	556.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	3.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	5,309.000
	0550- 60-224	FENCE GATE, TYPE B, DOUBLE, 18.1-20.0' OPENING	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	148,971.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	11,923.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	17.410
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.023
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,651.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,422.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	960.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.368
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.120
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.907
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	31.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	92.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	14.039
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,045.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.038
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.333
	0999- 16-	PARTNERING, DO NOT BID (25786235201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	25.000

**Call Order: 006 Proposal: T7402**

ALT	Item	Description	Unit	Quantity
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25786235201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	41.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	12.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (25786235201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.978
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,651.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,262.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	740.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.681
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	31.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	92.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	558.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.333
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,357.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	41.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	39.000
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.120
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.848
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.223
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.646
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	620.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	973.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	39.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	540.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000

**Call Order: 006 Proposal: T7402**

ALT	Item	Description	Unit	Quantity
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 14	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-60'	EA	1.000
	0649- 21- 25	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 78'-60'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	8.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	5.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0660- 1-101	LOOP DETECTOR INDUCTIVE, F&I, TYPE 1	EA	11.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	7.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	1.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-112	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0700- 11-321	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, REGULATORY SIGN, UP TO 12 SF	AS	2.000
<b>Section 0004 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (25786235601)	LS	1.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	243.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	4,173.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	2,825.000
	1050- 31-218	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 18"	LF	12,092.000
	1050- 31-224	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 24"	LF	10.000
	1050- 51-206	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 6"	LF	852.000
	1050- 51-208	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 8"	LF	613.000

**Call Order: 006 Proposal: T7402**

ALT	Item	Description	Unit	Quantity
	1050- 51-212	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12"	LF	178.000
	1050- 51-218	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 18"	LF	6,802.000
	1050- 51-224	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 24"	LF	48.000
	1050- 61-124	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 24"	LF	114.000
	1050- 61-130	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 30"	LF	702.000
	1055- 11-414	UTILITY FITTINGS, F&I, DI/CI, ELBOW, 8 - 19.9"	EA	204.000
	1055- 11-415	UTILITY FITTINGS, F&I, DI/CI, ELBOW, 20 - 49.9"	EA	3.000
	1055- 11-424	UTILITY FITTINGS, F&I, DI/CI, TEE, 8 - 19.9"	EA	33.000
	1055- 11-425	UTILITY FITTINGS, F&I, DI/CI, TEE, 20 - 49.9"	EA	1.000
	1055- 11-434	UTILITY FITTINGS, F&I, DI/CI, REDUCER, 8 - 19.9"	EA	3.000
	1055- 11-435	UTILITY FITTINGS, F&I, DI/CI, REDUCER, 20 - 49.9"	EA	2.000
	1055- 11-444	UTILITY FITTINGS, F&I, DI/CI, UNION, 8 - 19.9"	EA	13.000
	1055- 11-454	UTILITY FITTINGS, F&I, DI/CI, CAP/PLUG, 8 - 19.9"	EA	19.000
	1055- 11-455	UTILITY FITTINGS, F&I, DI/CI, CAP / PLUG, 20 - 49.9"	EA	1.000
	1080- 21-106	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 6"	EA	32.000
	1080- 21-108	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 8"	EA	18.000
	1080- 21-112	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 12"	EA	5.000
	1080- 21-118	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 18"	EA	29.000
	1080- 21-124	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 24"	EA	1.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	32.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	18.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	5.000
	1080- 24-118	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 18"	EA	29.000
	1080- 24-124	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 24"	EA	1.000
	1080- 25-102	UTILITY FIXTURE- BLOWOFF ASSEMBLY, FURNISH AND INSTALL, 2"	EA	2.000
	1080- 26-102	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 2"	EA	41.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	52.000
	1080- 29-108	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 8"	EA	114.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	114.000
	1080- 29-118	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 18"	EA	494.000
	1080- 29-124	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 24"	EA	1.000
	1080- 33-106	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 6"	EA	6.000
	1080- 33-108	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 8"	EA	1.000
	1080- 33-112	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 12"	EA	8.000
	1644-113- 08	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 1PUMPER, 6"	EA	14.000