

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180613 Call Order: 008 Proposal: T7413 District:07
 Counties: HILLSBOROUGH
 Road Name: SR 400 (I-4)
 Limits: FROM E OF SR 93A (I-75) TO E OF WILLIAMS RD AND FROM E OF 50TH ST TO E OF MCINTOSH RD
 Project(s): 43033515201 Federal Aid No: D717061B
 Project(s): 43658815201(*) Federal Aid No: D717060B
 Total Roadway Length: 24.725 Miles Contract Days: 480
 Total Bridge Length: 0.877 Miles Letting Date: 06/13/18
 Total Proposal Length: 25.606 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Calendar Days
 Proposal Budget Estimate: \$30,399,898.00

Please read the full advertisement

Description:

THERE WILL BE A MANDATORY PRE-BID MEETING FOR THIS PROJECT AT 1:30 PM EST ON MONDAY, MAY 14, 2018 AT THE FLORIDA DEPARTMENT OF TRANSPORTATION, DISTRICT SEVEN OFFICE, PRODUCTION, 11201 N MCKINLEY DR, TAMPA, FL 33612. IF YOU HAVE ANY QUESTIONS CONCERNING THIS MATTER, PLEASE CONTACT SANDRA GONZALEZ, P.E. AT (813) 975-6096.

THIS PRE-BID MEETING IS MANDATORY BECAUSE OF THE COMPLEXITY OF THE PROJECT. ONLY PLANS AND SPECIFICATIONS WILL BE AVAILABLE PRIOR TO THE PRE-BID MEETING. THE PROSPECTIVE BIDDER SHALL BE PREQUALIFIED ACCORDING TO THE REQUIREMENTS OF FDOT RULE CHAPTER 14-22 AND SECTION 2-1 OF THE 2017 STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

PROPOSALS (BIDDING DOCUMENTS) WILL BE ISSUED ONLY TO THE PROSPECTIVE BIDDERS WHO HAVE ATTENDED THE PRE-BID MEETING AND MET THE FLORIDA DEPARTMENT OF TRANSPORTATION QUALIFICATIONS FOR THIS PROJECT.

PROSPECTIVE BIDDERS ORDERING BID DOCUMENTS PRIOR TO THE PRE-BID MEETING WILL BE GIVEN ACCESS TO DOWNLOAD THE BID DOCUMENTS WITHIN 24 HOURS AFTER THE PRE-BID MEETING. THOSE PROSPECTIVE BIDDERS ORDERING THE DOCUMENTS AFTER THE PRE-BID MEETING WILL NEED TO CONTACT THE OFFICE ADVERTISING THE PROJECT TO CONFIRM ATTENDANCE AND RECEIVE ACCESS TO DOWNLOAD THE BID DOCUMENTS. PLEASE CONTACT THE OFFICE AT LEAST TWO WORKING DAYS PRIOR TO THE DEADLINE FOR OBTAINING BID DOCUMENTS TO ALLOW TIME FOR PROCESSING.

The improvements under this contract consist of milling and resurfacing, ramp reconstruction, minor drainage improvements, minor ITS, and signing and pavement markings on SR 400 (I-4) mainline and 38 ramps.

Call Order: 008 Proposal: T7413

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43033515201)	LS	1.000
	0101- 1-	MOBILIZATION (43658815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43033515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43658815201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43033515201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43033515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	4,644.000
	0102- 60-	WORK ZONE SIGN	ED	377,550.000
	0102- 71- 11	TEMPORARY BARRIER, F&I, CONCRETE	LF	1,178.000

Call Order: 008 Proposal: T7413

ALT	Item	Description	Unit	Quantity
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	3,853.000
	0102- 71- 21	TEMPORARY BARRIER, RELOCATE, CONCRETE	LF	5,350.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	5,356.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	97,651.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	18,969.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	982.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	16,318.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	55.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	12,515.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,200.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,200.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	3,176.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	3,176.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,844.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	274.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	524.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	262.000
	0104- 19-	CHEMICAL TREATMENT- POWDERED, FOR EROSION CONTROL	SY	180.000
	0107- 1-	LITTER REMOVAL	AC	5,274.140
	0107- 2-	MOWING	AC	4,177.690
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43033515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43033515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43658815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	647.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43658815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	10,074.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	75.000
	0120- 4-	SUBSOIL EXCAVATION	CY	2,034.000
	0120- 6-	EMBANKMENT	CY	9,610.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43658815201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	10,753.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	611.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	3,113.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	3,520.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	1,601.000
	0327- 70- 3	MILLING EXIST ASPH PAVT, 4 1/2" AVG DEPTH	SY	2,954.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	5,079.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	966.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	334,618.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	850.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	3,362.000
	0327- 70- 9	MILLING EXIST ASPH PAVT, 5 1/4" AVG DEPTH	SY	71,181.000

Call Order: 008 Proposal: T7413

ALT	Item	Description	Unit	Quantity
	0327- 70- 10	MILLING EXIST ASPH PAVT, 5" AVG DEPTH	SY	1,383.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	396,160.000
	0327- 70- 17	MILLING EXIST ASPH PAVT, 3 1/4" AVG DEPTH	SY	14,502.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	89,253.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	5,690.000
	0327- 70- 26	MILLING EXIST ASPH PAVT, 4 3/4" AVG DEPTH	SY	23,464.000
	0327- 70- 27	MILLING EXIST ASPH PAVT, 5 3/4" AVG DEPTH	SY	23,058.000
	0327- 70- 29	MILLING EXIST ASPH PAVT, 6 1/4" AVG DEPTH	SY	3,185.000
	0327- 70- 42	MILLING EXIST ASPH PAVT, 7 1/4" AVG DEPTH	SY	72,074.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	22,455.800
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	224.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	20,627.000
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	950.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	94,020.400
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	29,281.100
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	50.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	150.600
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	6.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	1.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	644.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	1,239.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	388.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	367.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	70.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	65.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	23.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	1.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	1.000
	0430-991-	MITERED END SECT, REPLACE SLAB- CONSTRUCTION USE	EA	14.000
	0455- 35- 13	STEEL PILING, HP 16 X 121	LF	1,275.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	8.100
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	238.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	411.000
	0521- 72- 3	SHOULDER CONCRETE BARRIER, RIGID-SHOULDER	LF	29.000
	0521- 72- 10	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 42"	LF	346.000
	0521- 72- 11	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 54"	LF	252.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	209.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	32.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	86.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	296.000

Call Order: 008 Proposal: T7413

ALT	Item	Description	Unit	Quantity
	0527- 2-	DETECTABLE WARNINGS	SF	227.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	51.500
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	36.000
	0530- 74-	BEDDING STONE	TN	10.400
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,278.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	6.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER CONNECTION, FURNISH & INSTALL	EA	23.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	7.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,768.000
	0536- 85- 22	GUARDRAIL END TREATMENT- FLARED APPROACH TERMINAL	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0546- 72- 55	RUMBLE STRIPS, GROUND-IN, 16" SHOULDER	GM	38.513
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	89,511.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,700.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,655.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	37.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	44.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	44.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	4.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	38.859
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.967
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	7.099
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,830.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	10,336.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,061.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	48.927
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	2.523
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.016
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	62.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	226.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	36.800
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	275.000
	0999- 16-	PARTNERING, DO NOT BID	LS	1.000

Call Order: 008 Proposal: T7413

ALT	Item	Description	Unit	Quantity
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	13.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43033515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43658815201)	LS	1.000
Section 0002 Signing				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	8.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	9.000
	0660- 3- 42	VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	105.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	79.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	4.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871 UP TO 12 SF	AS	1.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	156.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	6.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	18.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	18.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	9.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	76.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	20.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	1.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	1.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	1.000
	0700- 3-107	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 201-300 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	20.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	1.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	1.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	1.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	0.244
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	0.236
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	743.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	56.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43033515201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43658815201)	LS	1.000

Call Order: 008 Proposal: T7413

ALT	Item	Description	Unit	Quantity
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	7.436
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,051.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	10,336.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	206.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.016
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	51.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	226.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	12.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	275.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	855.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	11.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	15.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	34.616
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.967
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	48.927
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	2.523
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	34.094
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.366
	0713-103-103	PERMANENT TAPE, WHITE, SOLID LANE DROP MARKING, 12" FOR CONCRETE BRIDGES	GM	0.048
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.735
	0713-103-133	PERMANENT TAPE, WHITE, SKIP, 12" WIDE 3'-9' DROP LANE ON CONCRETE SURFACES	GM	0.109
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.210
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	1.400
	0713-103-333	PERMANENT TAPE, BLACK, 3'-9' DROP LANE, 12" ON CONCRETE SURFACES	GM	0.059