

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting: CT180328 Call Order: 002 Proposal: T1704 District:01  
Counties: COLLIER, LEE  
Road Name: SR 739 (US 41B)  
Limits: AT VARIOUS LOCATIONS AS LISTED IN THE PLANS  
Project(s): 44011615201(\*) Federal Aid No: D117090B  
Project(s): 44012815201 Federal Aid No: D117094B  
Total Roadway Length: 2.931 Miles Contract Days: 100  
Total Bridge Length: 0.000 Miles Letting Date: 03/28/18  
Total Proposal Length: 2.931 Miles Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 60 Days (Aqui Time)  
Proposal Budget Estimate: \$201,946.00

Please read the full advertisement

Description:

The improvements under this contract consist of highway lighting and sidewalks on State Road 739 (U.S. 41B) (Fowler Street) and the intersections of First Street, Pondella Road and State Road 78 (Pine Island Road), in Lee County and on State Road 29 (N. 15th Street) and the intersection of Immokalee Drive in Collier County.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: T1704**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44011615201)	LS	1.000
	0101- 1-	MOBILIZATION (44012815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44011615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	344.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	372.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	260.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	20.000
	0104- 10- 3	SEDIMENT BARRIER	LF	120.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	0.970
	0107- 2-	MOWING	AC	0.720
	0110- 1- 1	CLEARING & GRUBBING (44011615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44012815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	34.000
	0120- 1-	REGULAR EXCAVATION	CY	2.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	6.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	27.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	163.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44011615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012815201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	167.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	562.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	13.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	3,075.000
	0715- 4- 11	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT	EA	2.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	4.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	11.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	11.000
	0715-511-130	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 30'	EA	4.000