

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180328 Call Order: 004 Proposal: T2680 District:02
 Counties: COLUMBIA
 Road Name: SR 25 (US 441)
 Limits: FROM THE ALACHUA CO LINE TO SR 93 (I-75)
 Project(s): 43616415201(*) Federal Aid No: D217094B
 Total Roadway Length: 9.651 Miles Contract Days: 160
 Total Bridge Length: 0.013 Miles Letting Date: 03/28/18
 Total Proposal Length: 9.664 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days

Proposal Budget Estimate: \$5,389,366.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, highway signing and other incidental construction SR 25 (US 441) in Columbia County from Alachua County Line to SR 93 (I-75).

Call Order: 004 Proposal: T2680

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43616415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43616415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	13,120.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	1,450.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	35,200.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	4,776.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	320.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	160.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	214.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,923.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	770.910
	0107- 2-	MOWING	AC	720.910
	0110- 1- 1	CLEARING & GRUBBING (43616415201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.130
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	5.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	2,502.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43616415201)	LS	1.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	5,489.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	6,435.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	6,486.000

Call Order: 004 Proposal: T2680

ALT	Item	Description	Unit	Quantity
	0315- 1- 3	STRESS ABSORBING MEMBRANE, PROJECT NUMBER 436164-1-52-01	SY	3,068.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	9,342.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	900.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	558.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	3,068.000
	0327- 70- 12	MILLING EXIST ASPH PAVT, 1 1/4" AVG DEPTH	SY	143,713.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	35,247.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	16,961.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	16,428.200
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	240.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	60.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	37.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	6.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	152.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	86,626.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	41.130
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	148.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,352.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.108
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	68.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	17.147
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,618.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	9.612
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.110
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43616415201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	24.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	25.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	17.853
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	6.274
	0701- 18-221	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	4.238

Call Order: 004 Proposal: T2680

ALT	Item	Description	Unit	Quantity
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43616415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	74.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	676.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.053
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	31.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	529.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.059
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	70.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	7.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	7.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.969
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.845
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.508