

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180328 Call Order: 007 Proposal: T3637 District:03
Counties: OKALOOSA
Road Name: SR 4
Limits: FROM THE SANTA ROSA CO LINE TO 16TH ST
Project(s): 43626515201(*) Federal Aid No: D317070B
Total Roadway Length: 7.463 Miles Contract Days: 120
Total Bridge Length: 0.000 Miles Letting Date: 03/28/18
Total Proposal Length: 7.463 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 day Acquis.

Proposal Budget Estimate: \$3,722,052.00

Please read the full advertisement

Description:

The improvements under this contract consist of the milling and resurfacing of SR 4 from the Santa Rosa County Line to 16th Street. Existing travel lanes, auxiliary lanes, and paved shoulders will be resurfaced. Other work includes minor drainage improvements, guardrail upgrades, cross slope correction, signing and pavement markings, and pedestrian signal upgrades in Okaloosa County.

Call Order: 007 Proposal: T3637

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43626515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43626515201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	174.800
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	56.000
	0102- 60-	WORK ZONE SIGN	ED	6,240.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,400.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,840.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	480.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	30.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	30.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	120.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,198.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	360.000
	0107- 2-	MOWING	AC	164.000
	0110- 1- 1	CLEARING & GRUBBING (43626515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	206.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43626515201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	696.200
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43626515201)	LS	1.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	4,062.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	22.000

Call Order: 007 Proposal: T3637

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	110,903.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	12,870.900
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	10,691.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	154.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	4.100
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	12.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	4.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	2.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	3.000
	0430-990-	MITERED END SECT, REPLACE GRATE	EA	6.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	428.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	20.000
	0527- 2-	DETECTABLE WARNINGS	SF	77.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,025.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	22.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,975.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- FLARED	EA	11.000
	0536- 85- 24	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- PARALLEL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	26,477.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	15.104
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.027
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	426.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	64.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	83.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	8.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.334
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	78.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.241
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.089
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43626515201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	6.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000

Call Order: 007 Proposal: T3637

ALT	Item	Description	Unit	Quantity
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	13.771
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	4.991
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	12.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43626515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	426.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	64.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	83.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	8.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	78.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.089
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	334.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	15.104
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.027
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.343
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.241
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	395.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	194.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	20.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	5.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	4.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	4.000