

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180328	Call Order: 001	Proposal: T3646	District:03
Counties:	WAKULLA			
Road Name:	SR 369 (US 319)			
Limits:	FROM N OF SR 267 TO THE LEON COUNTY LINE			
Project(s):	22049585201(*)	Federal Aid No:	1991064P	
Project(s):	22049585601	Federal Aid No:	N/A	
Total Roadway Length:	2.243 Miles	Contract Days:	850	
Total Bridge Length:	0.000 Miles	Letting Date:	03/28/18	
Total Proposal Length:	2.243 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Calendar Days	

Proposal Budget Estimate: \$21,552,502.00

Please read the full advertisement

Description:

The improvements under this contract consist of the reconstruction of SR 369 including adding lanes, milling and resurfacing, earthwork, base work, drainage improvements, signing and pavement markings and utility work consisting of installation of a water line and fire hydrants.

Call Order: 001 Proposal: T3646

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (220049585201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (22049585201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (22049585201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (22049585201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (22049585201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (22049585201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (22049585201)	LS	1.000
	0102- 2- 6	SPECIAL DETOUR 6 (22049585201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	1,210.000
	0102- 60-	WORK ZONE SIGN	ED	82,584.000
	0102- 61-	BUSINESS SIGN	EA	2.000
	0102- 71- 11	TEMPORARY BARRIER, F&I, CONCRETE	LF	11,013.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	8,213.000
	0102- 71- 21	TEMPORARY BARRIER, RELOCATE, CONCRETE	LF	12,500.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	5,538.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	518,127.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	62,583.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	31,366.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	67.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	110.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	4,921.000
	0104- 10- 3	SEDIMENT BARRIER	LF	65,417.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	176.000

Call Order: 001 Proposal: T3646

ALT	Item	Description	Unit	Quantity
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	2,971.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	9.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	72.000
	0107- 1-	LITTER REMOVAL	AC	3,099.440
	0107- 2-	MOWING	AC	2,988.750
	0110- 1- 1	CLEARING & GRUBBING (22049585201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	24.000
	0120- 1-	REGULAR EXCAVATION	CY	223,752.000
	0120- 4-	SUBSOIL EXCAVATION	CY	10,350.000
	0120- 6-	EMBANKMENT	CY	440,547.000
	0120- 74-	SURCHARGE EMBANKMENT	CY	3,832.000
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	25.000
	0141- 71- 1	SETTLEMENT MONITORING ASSEMBLY- FLUID BASED, PROJECT 220495-8-52-01	AS	5.000
	0141- 72- 1	SETTLEMENT MONITORING DATA COLLECTION HUB, PROJECT 220495-8-52-01	AS	5.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	65,060.000
	0160- 4-	TYPE B STABILIZATION	SY	151,062.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	412,800.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	25,352.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	138.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	7,677.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	82,600.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	4,842.000
	0334- 1- 57	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, HIGH POLYMER	TN	15,969.200
	0337- 7- 26	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER	TN	3,972.300
	0337- 7- 92	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, HIGH POLYMER	TN	266.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.600
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	18.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	28.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	9.000
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	1.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	5.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	9.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	7.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	3.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	1,011.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	38.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	29.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	63.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	2,078.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	2,227.000

Call Order: 001 Proposal: T3646

ALT	Item	Description	Unit	Quantity
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,287.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	3,627.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	877.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	79.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	280.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/C	LF	221.000
	0430-175-242	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 42"S/C	LF	435.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	15.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	4.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 30" CD	EA	2.000
	0430-982-638	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 36" CD	EA	2.000
	0430-982-640	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 42" CD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	49.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	4.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	6.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	967.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	44.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	149.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	221.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	193.800
	0550- 60-112	FENCE GATE, TYPE A, SINGLE, 6.1-12.0' OPENING	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	367,563.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	212,722.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	19.248
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	219.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,385.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.114
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	22.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	21.469
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,281.000
	0751- 60- 1	TRAIL ROAD, NO 57 STONE, 6" MINIMUM, PROJECT 220495-8-52-01	SY	3,738.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	8.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22049585201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	39.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	29.000

Call Order: 001 Proposal: T3646

ALT	Item	Description	Unit	Quantity
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	8.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	11.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	41.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	13.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	65.000
	0705- 10- 4	OBJECT MARKER, TYPE 4	EA	4.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	13.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	64.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,439.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	436.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	57.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	504.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.232
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	5.206
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.515
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.503
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	5.261
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.096
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.761
Section 0003 Utilities				
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,200.000
	0908-104- 1	CONTRACTOR'S SEDIMENT AND EROSION CONTROL (22049585601)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22049585601)	LS	1.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	6,825.000
	1050- 31-202	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	40.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	6,685.000
	1050- 42-202	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	170.000
	1050- 42-206	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	1,765.000
	1080- 21-106	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 6"	EA	37.000

Call Order: 001 Proposal: T3646

ALT	Item	Description	Unit	Quantity
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	37.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	221.000
	1644-113- 08	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 1PUMPER, 6"	EA	11.000