

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT180328 Call Order: 009 Proposal: T4473 District:04
 Counties: PALM BEACH
 Road Name: SR 9 (I-95)
 Limits: FROM S OF L-30 CANAL TO N OF GATEWAY BLVD AND FROM S OF BOYNTON BEACH BLVD TO N OF GATEWAY BLVD
 Project(s): 42751615201(*) Federal Aid No: D417058B
 Project(s): 42751615202 Federal Aid No: D417058B
 Total Roadway Length: 4.895 Miles Contract Days: 335
 Total Bridge Length: 0.090 Miles Letting Date: 03/28/18
 Total Proposal Length: 7.644 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15
 Proposal Budget Estimate: \$12,904,358.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, drainage improvements, curb and gutter, sidewalks, driveways, detectable warnings, guardrail, rumble strips, signing and pavement markings, and traffic monitoring sites along State Road 9 (I-95) inclusive of southbound I-95 from south of L-30 Canal to north of Gateway Boulevard, and northbound I-95 from south of Boynton Beach Boulevard to north of Gateway Boulevard, for 7.644 miles (includes Interstate connection ramp numbers 93220-026, 93220-027, 93220-029, 93220-030, 93220-031, 93220-032, 93220-137, 93220-138, 93220-139, and 93220-140) in the City of DelRay Beach and the City of Boynton Beach, Palm Beach County.

Call Order: 009 Proposal: T4473

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (42751615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42751615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	16,720.000
	0102- 60-	WORK ZONE SIGN	ED	58,620.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871	ED	3,030.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	318,545.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	4,540.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	168.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,235.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	9,789.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	7,038.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	670.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	590.000
	0104- 10- 3	SEDIMENT BARRIER	LF	40,367.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,559.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	219.000
	0107- 1-	LITTER REMOVAL	AC	1,358.860
	0107- 2-	MOWING	AC	959.970
	0110- 1- 1	CLEARING & GRUBBING (42751615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (42751615202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	36.000

Call Order: 009 Proposal: T4473

ALT	Item	Description	Unit	Quantity
	0120- 1-	REGULAR EXCAVATION	CY	30.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	372.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	96,882.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	13,782.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	337,303.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	811.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	10,599.300
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	48,079.900
	0334- 1- 58	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, HIGH POLYMER	TN	1,437.900
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	13,019.200
	0337- 7- 26	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER	TN	440.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	173.000
	0425- 5-	MANHOLE, ADJUST	EA	83.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	59.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	7.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	23.000
	0527- 2-	DETECTABLE WARNINGS	SF	141.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	812.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER- BRIDGE ANCHORAGE ASSEMBLY CONNECTION, FURNISH & INSTALL	EA	3.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	1.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- FLARED	EA	6.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- TYPE II	EA	5.000
	0538- 1-	GUARDRAIL RESET	LF	2,644.000
	0544- 75- 1	CRASH CUSHION	EA	1.000
	0546- 72- 55	RUMBLE STRIPS, GROUND-IN, 16" SHOULDER	GM	12.723
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	16,353.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	710.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	910.000
	0632- 7- 7	SIGNAL CABLE, REMOVE- OUTSIDE OF INTERSECTION	LF	450.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	25.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	25.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	3.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	3.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.853
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.886

Call Order: 009 Proposal: T4473

ALT	Item	Description	Unit	Quantity
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	3.435
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	403.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	53.206
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	103.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	92.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.715
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	7.045
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	13,273.000
	0999- 16-	PARTNERING, DO NOT BID (42751615201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	11.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42751615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42751615202)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	3.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	3.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870, 12-20 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	21.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	91.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	31.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42751615201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	2.572
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	462.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	52.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.006
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	68.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	72.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	13,103.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	152.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	15.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	31.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	27.000

Call Order: 009 Proposal: T4473

ALT	Item	Description	Unit	Quantity
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	39.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	9.423
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.654
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	35.586
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.268
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	2.716
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	7.047
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.649
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.839
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.148
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.839
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	33,847.000