

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180328 Call Order: 013 Proposal: T6420 District:06
 Counties: MIAMI-DADE
 Road Name: SR 5 (US 1)
 Limits: FROM SW 37TH AVE TO PONCE DE LEON BRIDGE 879026 AND AT RIVIERA DR

Project(s): 43345515201(*) Federal Aid No: D617072B
 Project(s): 43345515202 Federal Aid No: D617072B
 Project(s): 43345515601 Federal Aid No: N/A
 Project(s): 43345525201 Federal Aid No: D617073B
 Project(s): 43345525202 Federal Aid No: D617073B
 Project(s): 43345525203 Federal Aid No: D617073B

Total Roadway Length: 0.559 Miles Contract Days: 400
 Total Bridge Length: 0.003 Miles Letting Date: 03/28/18
 Total Proposal Length: 0.562 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 90 Calendar Days

Proposal Budget Estimate: \$5,756,701.00

Please read the full advertisement

Description: Incentive / Disincentive

This contract consists of intersection improvements along SR 5 (US 1).

Call Order: 013 Proposal: T6420

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	5.700
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	21.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	862.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	7,445.000
	0455- 88- 5	DRILLED SHAFT, 48" DIA	LF	162.000
	0455-122- 5	EXCAVATION UNCLASSIFIED SHAFT, 48" DIA	LF	162.000
	0455-142-	CROSSHOLE SONIC LOGGING	EA	5.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	34.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43345515201 879026)	LS	1.000
	0460- 2- 15	STRUCT STEEL, MISCELLANEOUS (43345515201 879026)	LS	1.000
	0460- 7-	PREFABRICATED STEEL PEDESTRIAN BRIDGE	SF	1,553.000
	0750- 1- 17	ARCHITECTURAL, BUILDING, NEW, STORAGE/MECHANICAL (43345515201 879026)	LS	1.000
	0750- 1- 19	ARCHITECTURAL, BUILDING, NEW, OTHER BUILDING (43345515201 879026)	LS	1.000
	0750- 1- 60	ARCHITECTURAL, BUILDING, REMOVE (43345515201 879026)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43345515201)	LS	1.000
	0101- 1-	MOBILIZATION (43345525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43345515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43345525201)	LS	1.000

Call Order: 013 Proposal: T6420

ALT	Item	Description	Unit	Quantity
	0102- 2- 1	SPECIAL DETOUR 1 (43345515201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43345525201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43345515201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43345525201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	18.600
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	488.000
	0102- 60-	WORK ZONE SIGN	ED	49,400.000
	0102- 61-	BUSINESS SIGN	EA	20.000
	0102- 71- 11	TEMPORARY BARRIER, F&I, CONCRETE	LF	2,889.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	2,362.000
	0102- 71- 21	TEMPORARY BARRIER, RELOCATE, CONCRETE	LF	1,527.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	1,992.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	62,640.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	5,020.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	4,147.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,160.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,452.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	14.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,176.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,200.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,200.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	53.000
	0107- 1-	LITTER REMOVAL	AC	25.180
	0107- 2-	MOWING	AC	11.310
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43345515201)	LS	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43345525201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43345515201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43345525201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43345515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43345525201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,686.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43345515201)	LS	1.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43345525201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	4,011.100
	0120- 6-	EMBANKMENT	CY	646.800
	0160- 4-	TYPE B STABILIZATION	SY	7,045.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	2,110.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	5,865.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	3,596.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	18,484.000

Call Order: 013 Proposal: T6420

ALT	Item	Description	Unit	Quantity
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,984.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2,200.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	0.700
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	4.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	20.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	8.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	6.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	13.000
	0430-175-112	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"S/CD	LF	4.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	54.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	2,015.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	8.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	8,334.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	253.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	127.000
	0521- 72- 11	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 54"	LF	82.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,599.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	499.000
	0527- 2-	DETECTABLE WARNINGS	SF	238.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY/END TREATMENT- TYPE II	EA	1.000
	0538- 1-	GUARDRAIL RESET	LF	18.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	58.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,563.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	95.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	6.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	6.000
	0695- 7-141	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 4, BASE MOUNT	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.062
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,908.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	980.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.981
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.456
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000

Call Order: 013 Proposal: T6420

ALT	Item	Description	Unit	Quantity
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	19.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.256
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	10.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.104
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	58.000
	0914-550- 11	FENCING- PEDESTRIAN BARRIER, FURNISH AND INSTALL 4', PROJECT 433455-1-52-01	LF	72.000
	0914-550- 12	FENCING- PEDESTRIAN BARRIER, FURNISH AND INSTALL 8', PROJECT 433455-1-52-01	LF	617.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43345515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43345525201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	23.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	42.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43345515201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43345525201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.009
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,961.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	33.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	670.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.205
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	30.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	29.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.146
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,554.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.791
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.781

Call Order: 013 Proposal: T6420

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.174
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,935.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,298.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	30.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	18,307.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	464.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	27.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	27.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43345515202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43345525203)	LS	1.000
Section 0005 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	4,020.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	1,861.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	79.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	3,810.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	10.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	5.000
	0650- 1- 14	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	8.000
	0650- 1- 18	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000

Call Order: 013 Proposal: T6420

ALT	Item	Description	Unit	Quantity
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	6.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	5.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	19.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	2.000
	0670- 5-121	TRAFFIC CONTROLLER ASSEMBLY, F&I, 170, 1 PREEMPTION PLAN	AS	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 12- 12	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, TWO BEACONS	AS	2.000
Section 0006 Landscape / Peripheral				
	0580- 2- 2	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK	EA	25.000
	0590- 70-	IRRIGATION SYSTEM (43345525202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43345525202)	LS	1.000
Section 0007 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43345515601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	5.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	7.000
Section 0008 Intelligent Transportation System				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,760.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	580.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	17,540.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	18,390.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	204.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	4.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	12.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	4.000
	0682- 1-600	ITS CCTV CAMERA,, REMOVE & DISPOSAL	EA	4.000