

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180523 Call Order: 008 Proposal: T1705 District:01
Counties: MANATEE, SARASOTA
Road Name: SR 45 AND SR 780
Limits: AT VARIOUS LOCATIONS AS LISTED IN THE PLANS
Project(s): 44012615201 Federal Aid No: D117093B
Project(s): 44013315201(*) Federal Aid No: D117095B
Project(s): 44013715201 Federal Aid No: D117097B
Total Roadway Length: 4.672 Miles Contract Days: 110
Total Bridge Length: 0.000 Miles Letting Date: 05/23/18
Total Proposal Length: 4.672 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 90 Days (Aqui Time)
Proposal Budget Estimate: \$531,676.00

Please read the full advertisement

Description:

The improvements under this contract consist of highway lighting and sidewalk SR 45 at the intersections of 30th Ave W., 21st Ave W., 17th Ave. W., 12th Ave. W., 9th Ave. W., 23rd St E., 17th St. E., 13th Ave. E., and 9th Ave E. in Manatee County and along SR 780 at the intersection of East Ave. in Sarasota County.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 008 Proposal: T1705

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44012615201)	LS	1.000
	0101- 1-	MOBILIZATION (44013315201)	LS	1.000
	0101- 1-	MOBILIZATION (44013715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44012615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44013315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44013715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,806.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,131.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	485.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	62.000
	0104- 10- 3	SEDIMENT BARRIER	LF	37.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	21.000
	0107- 1-	LITTER REMOVAL	AC	1.130
	0107- 2-	MOWING	AC	0.360
	0110- 1- 1	CLEARING & GRUBBING (44012615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44013315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44013715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	134.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	120.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44012615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44013315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44013715201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	379.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,715.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	36.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	10,858.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	936.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	18.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	4.000
	0715- 4- 22	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 35' MOUNTING HEIGHT	EA	5.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	3.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	20.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	28.000