

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180523 Call Order: 001 Proposal: T1709 District:01
 Counties: MANATEE
 Road Name: SR 93 (I-75)
 Limits: AT THE INTERSECTION OF SR 70
 Project(s): 20103225201(*) Federal Aid No: D117115B
 Project(s): 20103225601 Federal Aid No: D117115B
 Project(s): 20103225602 Federal Aid No: D117115B
 Total Roadway Length: 0.702 Miles Contract Days: 1100
 Total Bridge Length: 0.057 Miles Letting Date: 05/23/18
 Total Proposal Length: 0.759 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days
 Proposal Budget Estimate: \$92,951,547.00

Please read the full advertisement

Description: A+B Bidding/Incentive-Disincentive

The improvements under this contract consist of adding lanes, milling and resurfacing, widening, base work, interchange ramp modifications, drainage improvements, curb and gutter, guardrail, sidewalks, replacing bridge numbers 130154, 130155, 130065 and 130066, signing and pavement marking, signalization, intelligent transportation system, lighting and Utility Work by Highway Contractor on State Road 93 and the intersection of State Road 70 in Manatee County.

NOTE: This is a cost plus time proposal(A+B). The following sites are cost plus time sites.

Site	Description	Road Cost Per Day	Maximum Days
00	Contract Time	10000.00	1100

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (20103225201 Bridge No. 130065)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (20103225201 Bridge No. 130066)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (20103225201 Bridge No. 130154)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (20103225201 Bridge No. 130155)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	1,303.200
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	352.900
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	345.600
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	296.300
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	1,845.000
	0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER	SY	3,279.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	35.100
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	402,284.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	123,425.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	69,832.000
	0450- 1- 1	PRESTRESSED BEAMS, TYPE II	LF	2,287.000
	0450- 2- 63	PREST BEAMS: FLORIDA-I BEAM 63"	LF	2,600.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	3,664.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	3,210.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	450.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	360.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	376.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	452.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	367.000
	0521- 5- 1	CONCRETE TRAFFIC RAILING- BRIDGE, 32" F - SHAPE	LF	2,436.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	60.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (20103225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20103225201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (20103225201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (20103225201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	544.000
	0102- 60-	WORK ZONE SIGN	ED	141,655.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	137,249.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	38,360.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	315,692.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	10,925.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,775.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	20,343.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	53.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,987.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	3,900.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	3,900.000
	0104- 10- 3	SEDIMENT BARRIER	LF	15,973.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	9,455.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	9.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	192.000
	0107- 1-	LITTER REMOVAL	AC	764.310
	0107- 2-	MOWING	AC	764.310
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (20103225201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (20103225201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	17,187.000
	0120- 1-	REGULAR EXCAVATION	CY	357,983.000
	0120- 4-	SUBSOIL EXCAVATION	CY	9,776.000
	0120- 6-	EMBANKMENT	CY	539,501.000
	0160- 4-	TYPE B STABILIZATION	SY	402,724.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	8,314.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	29,230.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	20,923.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	25,848.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	160,627.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	107,599.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	4,466.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	19,195.000
	0327- 70- 9	MILLING EXIST ASPH PAVT, 5 1/4" AVG DEPTH	SY	620.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	44,869.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	162,326.000
	0327- 70- 17	MILLING EXIST ASPH PAVT, 3 1/4" AVG DEPTH	SY	8,469.000
	0327- 70- 20	MILLING EXIST ASPH PAVT, 3 3/4" AVG DEPTH	SY	10,727.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	2,200.000
	0327- 70- 23	MILLING EXIST ASPH PAVT, 6" AVG DEPTH	SY	2,200.000
	0327- 70- 26	MILLING EXIST ASPH PAVT, 4 3/4" AVG DEPTH	SY	10,436.000
	0327- 70- 27	MILLING EXIST ASPH PAVT, 5 3/4" AVG DEPTH	SY	1,700.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	8,892.400
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	6,956.600
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	11,527.700
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	90,175.600
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	19,484.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3,079.900
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	16.300
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	270.700
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	41,138.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	9.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	10.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	3.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	11.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	8.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	3.000
	0425- 1-545	INLETS, DITCH BOTTOM, TYPE D, PARTIAL	EA	2.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	15.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	14.000
	0425- 1-704	INLETS, GUTTER, TYPE S, J BOTTOM, >10'	EA	1.000
	0425- 1-801	INLETS, MEDIAN BARRIER, TYPE 1, <10'	EA	5.000
	0425- 1-891	INLETS, BARRIER WALL, <10'	EA	13.000
	0425- 1-892	INLETS, BARRIER WALL, >10'	EA	5.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	45.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	10.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	3.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	5.000
	0425- 78-	INLET CAP, PRECAST	EA	2.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	100.000
	0430-174-236	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 36"SD	LF	136.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	6,415.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	3,736.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	371.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	598.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	705.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	51.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	48.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	160.000
	0430-185-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 18" , STORM AND CROSS DRAIN	LF	266.000
	0430-185-130	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 30", STORM AND CROSS DRAIN	LF	124.000
	0430-185-136	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 36", STORM AND CROSS DRAIN	LF	159.000
	0430-611-225	U-ENDWALL WITH BAFFLES, STD 261, 1:3 SLOPE, 18"PIPE	EA	2.000
	0430-611-325	U-ENDWALL WITH BAFFLES, STD 261, 1:2 SLOPE, 18"PIPE	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	66.200
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	23.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	14.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	3.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	1.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	1.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	2.000
	0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	2.000
	0440- 1- 50	UNDERDRAIN, TYPE V	LF	1,255.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	156.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	19,799.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	2,127.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	4,794.000
	0521- 1-	MEDIAN CONCRETE BARRIER WALL	LF	1,553.000
	0521- 7- 1	CONCRETE TRAFFIC RAILING BARRIER-RETAINING WALL SYSTEM, F SHAPE WITH SOUND/NOISE BARRIER WALL, 8' HEIGHT	LF	940.000
	0521- 8- 1	CONCRETE TRAFFIC RAILING BARRIER WITH JUNCTION SLAB, 32" F SHAPE	LF	8,183.000
	0521- 72- 10	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 42"	LF	954.000
	0521- 72- 20	SHOULDER CONCRETE BARRIER WALL, F SHAPED, WITH 8' SOUND/NOISE WALL	LF	910.000
	0521- 72- 23	SHOULDER CONCRETE BARRIER WALL, F SHAPED, WITH 14' SOUND/NOISE WALL	LF	2,091.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,453.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	33.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	1,534.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	955.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	122.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0527- 2-	DETECTABLE WARNINGS	SF	334.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	180.500
	0530- 74-	BEDDING STONE	TN	127.900
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	319,140.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	39,000.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	19,061.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	19,061.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	8.000
	0536- 8- 12	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	EA	6.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	12.000
	0536- 73-	GUARDRAIL REMOVAL	LF	7,839.000
	0536- 85- 22	GUARDRAIL END TREATMENT- FLARED APPROACH TERMINAL	EA	21.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	14.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	2.000
	0544- 75- 1	CRASH CUSHION	EA	6.000
	0546- 72- 55	RUMBLE STRIPS, GROUND-IN, 16" SHOULDER	GM	24.428
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	110,134.000
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	84,323.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	538,034.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	61.546
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.772
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	7,649.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	939.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	671.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	66.759
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.007
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	11.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	128.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	43.750
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.033
	0999- 16-	PARTNERING, DO NOT BID (20103225201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	37.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20103225201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	40.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	28.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	7.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	82.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	8.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	9.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	18.000
	0700- 2- 18	MULTI- POST SIGN, F&I GROUND MOUNT, 301-400 SF	AS	1.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	40.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	4.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	5.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	3.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	2.000
	0700- 3-210	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 501-600 SF	EA	1.000
	0700- 3-211	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 601 SF AND GREATER	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	4.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 3-625	SIGN PANEL, REMOVE, 51-100 SF WITH LIGHTING	EA	4.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	3.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	3.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	9.000
	0700- 4-127	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 151-200 FT	EA	1.000
	0700- 4-140	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, OVERPASS BRIDGE MOUNT	EA	1.000
	0700- 4-610	OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER	EA	4.000
	0700- 4-620	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	EA	2.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	2.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	8.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	3.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	6.000
	0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	7,603.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	499.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	296.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20103225201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,691.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,294.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	783.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.940

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	56.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	184.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	724.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.095
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	90.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	23.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	22.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	18.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	19.521
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.258
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	40.610
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	2.620
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	16.553
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.793
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	10,450.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,710.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	77.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	58.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	15,650.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	25,300.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	12,250.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	9,822.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	10.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	16.000
	0715- 19- 13	HIGH MAST LIGHT POLE, FURNISH AND INSTALL, 120'	EA	15.000
	0715- 19- 60	HIGH MAST LIGHT POLE, REMOVE POLE AND FOUNDATION	EA	12.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	10.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	15.000
Section 0005 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	6,925.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,870.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	10.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	5,489.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	7,895.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	6,679.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	204.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	3.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	1.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	1.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	2.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	3.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	3.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	1,145.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	71.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	15.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	3.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,302.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 14	PRESTRESSED CONCRETE POLE, F&I, TYPE P-IV	EA	4.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	18.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	8.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	4.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	4.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	5.000
	0650- 1- 14	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	28.000
	0650- 1- 34	TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	7.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	13.000
	0660- 3- 42	VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	2.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	12.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	7.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	14.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	4.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	1.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	2.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	3.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	4.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	8.000
	0695- 3- 11	TRAFFIC MONITORING SITE SPEED/CLASSIFICATION UNIT, FURNISH & INSTALL, VOLUME SPEED AND CLASSIFICATION	AS	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	8.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	10.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0700- 11-321	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, REGULATORY SIGN, UP TO 12 SF	AS	2.000
Section 0006 Utilities				
	0000-700- 1	UTILITIES DESIGN GROUP- GENERIC PAY ITEM 1 ((Furnish & Install, Concrete Slab and Rebedding)(LF) 20103225601)	ZZ	853.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,984.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	4,380.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	1,500.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	6,364.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	288.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	2.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	28.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	15.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20103225601)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20103225602)	LS	1.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	390.000
	1050- 16-005	UTILITY PIPE,REMOVE & DISPOSE, 20-49.9"	LF	257.000
	1050- 31-218	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 18"	LF	29.000
	1050- 51-206	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 6"	LF	131.000
	1050- 51-224	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 24"	LF	133.000
	1050- 51-236	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 36"	LF	252.000
	1050- 61-136	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 36"	LF	23.000
	1050- 61-154	UTILITY PIPE- STEEL, FURNISH & INSTALL, CASING, 54"	LF	458.000
	1055- 51-118	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 18"	EA	4.000
	1055- 51-124	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 24"	EA	5.000
	1055- 51-136	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 36"	EA	2.000
	1055- 51-236	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 36"	EA	1.000
	1055- 51-436	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL UNION, 36"	EA	2.000
	1055- 51-524	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL, CAP/PLUG, 24"	EA	1.000
	1080- 23-136	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 36"	EA	2.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	1.000
	1080- 24-124	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 24"	EA	3.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	12.000
	1080- 26-500	UTILITY FIXTURE, VAC/AIR ASSEMBLY, ADJUST/MODIFY	EA	2.000
	1080- 27-118	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 18"	EA	2.000
	1080- 27-136	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 36"	EA	2.000
	1080- 32-124	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 24"	EA	2.000
	1644-133- 08	FIRE HYDRANT, F&I, TRAFFIC, 2 HOSE, 1PUMPER, 6"	EA	2.000
	1644-900-	FIRE HYDRANT, REMOVE	EA	2.000
Section 0007 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,536.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,251.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	45.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	7,809.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	39,292.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	315.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	42,168.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	268.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	272.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	21.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	23.000

Call Order: 001 Proposal: T1709

ALT	Item	Description	Unit	Quantity
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	4.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	12.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	1.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	8.000
	0633- 3- 56	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY PATCH PANEL	EA	19.000
	0633- 8- 4	MULTI-CONDUCTOR COMMUNICATION CABLE, RELOCATE	LF	315.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	15.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	4,949.000
	0639- 2- 4	ELECTRICAL SERVICE WIRE, RELOCATE	LF	324.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	3,848.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	9.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	8.000
	0641- 2- 13	PRESTRESSED CONCRETE POLE, F&I, TYPE P-III	EA	7.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	1.000
	0641- 3-186	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 86'	EA	1.000
	0641- 3-800	CONCRETE CCTV POLE, COMPLETE POLE REMOVAL	EA	2.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	5.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	6.000
	0660- 3- 42	VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	4.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	4.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	5.000
	0676- 2-600	ITS CABINET- REMOVE	EA	3.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	4.000
	0684- 2- 1	DEVICE SERVER, FURNISH & INSTALL	EA	4.000
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	4.000
	0687- 1- 60	HIGHWAY ADVISORY RADIO, REMOVE	EA	3.000