

Call Order: 002 Proposal: T3660

ALT	Item	Description	Unit	Quantity
	0510- 1- 4	NAVIGATION LIGHTS- FIXED BRIDGE, REPAIR/REHAB	EA	12.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	1,468.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	448.000
	0521- 5- 1	CONCRETE TRAFFIC RAILING- BRIDGE, 32" F - SHAPE	LF	1,468.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	1,468.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	9.600
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	915.800
	0530- 74-	BEDDING STONE	TN	366.300
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (40619435201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40619435201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (40619435201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (40619435201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (40619435201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (40619435201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (40619435201)	LS	1.000
	0102- 2- 6	SPECIAL DETOUR 6 (40619435201)	LS	1.000
	0102- 2- 7	SPECIAL DETOUR 7 (40619435201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,280.000
	0102- 60-	WORK ZONE SIGN	ED	60,420.000
	0102- 61-	BUSINESS SIGN	EA	1.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	936.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	1,593.000
	0102- 71- 24	TEMPORARY BARRIER, RELOCATE, TYPE K	LF	1,548.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	79,890.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	6,800.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	159.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,500.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	850.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	6.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,870.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,180.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	2,480.000
	0102-912- 1	PAVT MARKING REMOVABLE TAPE, YELLOW, SKIP	LF	2,903.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	297.000
	0104- 10- 3	SEDIMENT BARRIER	LF	742.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	484.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	320.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	57.200
	0107- 2-	MOWING	AC	17.800

Call Order: 002 Proposal: T3660

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (40619435201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (40619435201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (40619435201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	312.000
	0120- 1-	REGULAR EXCAVATION	CY	358.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	339.000
	0160- 4-	TYPE B STABILIZATION	SY	1,013.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	2,065.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	881.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	8,797.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	121.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	798.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	9.600
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	212.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,057.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	164.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	112.000
	0521- 72- 5	SHOULDER CONCRETE BARRIER WALL, RIGID-CURB & GUTTER	LF	19.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	275.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	7.000
	0527- 2-	DETECTABLE WARNINGS	SF	115.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	100.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	44.000
	0536- 8- 12	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	268.000
	0536- 85- 22	GUARDRAIL END TREATMENT- FLARED APPROACH TERMINAL	EA	1.000
	0544- 75- 1	CRASH CUSHION	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	341.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,426.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.628
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.102
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	661.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	280.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	467.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.626
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	4.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.588

Call Order: 002 Proposal: T3660

ALT	Item	Description	Unit	Quantity
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.158
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	12.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40619435201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870, UP TO 12 SF	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	6.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (40619435201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	411.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	280.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	74.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	4.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.158
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.322
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.102
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.435
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.311
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.259
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.259
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.259
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.259
Section 0004 Lighting				
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (40619435201)	LS	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	20.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	190.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000