

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180523 Call Order: 013 Proposal: T3669 District:03
 Counties: BAY
 Road Name: 36TH ST
 Limits: FROM MP 0.176 TO MP 0.188
 Project(s): 43046415201(*) Federal Aid No: D317005B
 Total Roadway Length: 1.116 Miles Contract Days: 145
 Total Bridge Length: 0.012 Miles Letting Date: 05/23/18
 Total Proposal Length: 0.128 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Days Acquis.

Proposal Budget Estimate: \$1,152,386.00

Please read the full advertisement

Description:

The improvements under this contract consist of constructing Bridge No. 465144 over Bayou, removal of the existing Bridge No. 466001, reconstruction of the bridge approaches and Pavement Markings on 36th Street in Bay County from MP 0.176 to MP 0.188.

Call Order: 013 Proposal: T3669

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43046415201)	LS	1.000
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	46.700
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	41.700
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	7.200
	0400- 4- 47	CONCRETE CLASS IV, CAST IN PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	44.300
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	179.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	4.600
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	10,784.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	4,734.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	703.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	8,282.000
	0450- 8- 12	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 52-54"	LF	363.000
	0455- 35- 22	STEEL PILING, 24" DIA. PIPE	LF	702.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	1,188.000
	0455-144- 22	TEST PILES - STEEL, 24" DIA PIPE	LF	278.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I Poured joint with backer rod	LF	77.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	1.300
	0521- 5- 1	CONCRETE TRAFFIC RAILING- BRIDGE, 32" F - SHAPE	LF	207.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	50.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43046415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43046415201)	LS	1.000

Call Order: 013 Proposal: T3669

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	2,030.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	28.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	580.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	7.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,650.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	235.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43046415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43046415201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,241.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	220.300
	0120- 5-	CHANNEL EXCAVATION	CY	220.000
	0160- 4-	TYPE B STABILIZATION	SY	6,356.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	969.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	82.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	5,796.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	475.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	945.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	653.700
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	87.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	16.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	3.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,469.000
Section 0003 Signing				
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43046415201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.091
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.091
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024