



**Call Order: 004 Proposal: T4477**

ALT	Item	Description	Unit	Quantity
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	62.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	724.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,213.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	38.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	11,372.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,384.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,384.000
	0104- 10- 3	SEDIMENT BARRIER	LF	34,703.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	6,454.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	14.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	106.000
	0107- 1-	LITTER REMOVAL	AC	759.620
	0107- 2-	MOWING	AC	514.170
	0110- 1- 1	CLEARING & GRUBBING (23025665201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (23025665202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (23025675201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,199.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	3.000
	0110- 73-	REMOVE EXISTING BULKHEAD	LF	1,245.000
	0120- 1-	REGULAR EXCAVATION	CY	300,204.000
	0120- 4-	SUBSOIL EXCAVATION	CY	18,141.000
	0120- 5-	CHANNEL EXCAVATION	CY	16,621.000
	0120- 6-	EMBANKMENT	CY	221,546.000
	0120- 74-	SURCHARGE EMBANKMENT	CY	36,694.000
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	21.000
	0145- 1-	GEOSYNTHETIC REINFORCED SOIL SLOPE	SF	175,180.000
	0160- 4-	TYPE B STABILIZATION	SY	216,935.000
	0173- 79- 6	SOIL STABILIZATION/IMPROVEMENT BY COLUMN SUPPORTED EMBANKMENT, PROJECT 230256-6-52-01 (23025665201)	LS	1.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	80,702.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	2,227.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	23,612.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	84,612.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	15,276.000
	0334- 1- 11	SUPERPAVE ASPHALTIC CONC, TRAFFIC A	TN	1,534.100
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,019.400
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	7,593.500
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,960.600
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	7,097.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	3,502.900
	0337- 7- 85	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	TN	1,663.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	820.800
	0350- 3- 8	PLAIN CEMENT CONCRETE PAVEMENT, 9.5"	SY	59,449.000

**Call Order: 004 Proposal: T4477**

ALT	Item	Description	Unit	Quantity
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT:	LF	110,175.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	59,449.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	73.900
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	18.600
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	2,076.100
	0400- 2- 2	CONCRETE CLASS II, ENDWALLS	CY	51.600
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	115.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	618,394.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	15,506.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	2.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	32.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	2.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	36.000
	0425- 1-362	INLETS, CURB, TYPE P-6, >10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	4.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	12.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	4.000
	0425- 1-462	INLETS, CURB, TYPE J-6, >10'	EA	4.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	3.000
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	2.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	14.000
	0425- 1-552	INLETS, DT BOT, TYPE E, >10'	EA	2.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	3.000
	0425- 1-562	INLETS, DT BOT, TYPE F, >10'	EA	1.000
	0425- 1-582	INLETS, DT BOT, TYPE H, >10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	8.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	5.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	16.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	29.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	935.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	148.000
	0430- 94- 5	DESILTING PIPE, 61" OR GREATER	LF	205.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	28.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	366.000
	0430-174-236	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 36"SD	LF	100.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	4,649.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	2,929.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,024.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	7,673.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	3,771.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	3,293.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	2,414.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	396.000
	0430-175-166	PIPE CULVERT, OPT MATERIAL, ROUND, 66"S/CD	LF	62.000

**Call Order: 004 Proposal: T4477**

ALT	Item	Description	Unit	Quantity
	0430-175-172	PIPE CULVERT, OPT MATERIAL, ROUND, 72"S/CD	LF	102.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	117.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	521.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	198.000
	0430-175-236	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/C	LF	291.000
	0430-175-248	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/C	LF	187.000
	0430-610-233	U-ENDWALL, STD 261, 1:3 SLOPE, 30"PIPE	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	643.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	99.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	1.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	1.000
	0430-982-143	MITERED END SECTION, OPTIONAL ROUND, 60" CD	EA	1.000
	0430-982-144	MITERED END SECTION, OPTIONAL ROUND, 66" CD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	1.000
	0430-984-141	MITERED END SECTION , OPTIONAL ROUND, 48" SD	EA	1.000
	0430-984-143	MITERED END SECTION , OPTIONAL ROUND, 60" SD	EA	1.000
	0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	4.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	11,345.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	1,815.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	595.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	44,048.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	965.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	4,859.000
	0520- 5- 21	TRAFFIC SEPARATOR - CONCRETE, TYPE II, 4' WIDE	LF	1,907.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	432.000
	0521- 72- 11	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 54"	LF	600.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	11,304.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,503.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	723.000
	0524- 2- 29	CONCRETE SLOPE PAVEMENT, 4", REINFORCED	SY	110.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,203.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	67,018.200
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	374.000
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	194.000
	0530- 74-	BEDDING STONE	TN	26,645.200
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	12,404.000
	0536- 73-	GUARDRAIL REMOVAL	LF	20,442.000
	0536- 85- 22	GUARDRAIL END TREATMENT- FLARED APPROACH TERMINAL	EA	3.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	7.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	4.000

**Call Order: 004 Proposal: T4477**

ALT	Item	Description	Unit	Quantity
	0544- 75- 1	CRASH CUSHION	EA	2.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	6,418.000
	0550- 10-228	FENCING, TYPE B, 5.1-6.0, RESET EXISTING	LF	3,886.000
	0550- 60-234	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 18.1-20.0' OPENING	EA	3.000
	0550- 60-235	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 20.1-24' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	147,657.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	14.375
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.320
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,639.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	319.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,003.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.882
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.501
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	96.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	14.266
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	713.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.330
	0916-530- 5	REVETMENT SYSTEMS- FABRIC FORMED CONCRETE RIPRAP, PROJECT 230256-6-52-01	SY	8,931.000
	0999- 16-	PARTNERING, DO NOT BID (23025665201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	45.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (23025665201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (23025665202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (23025675201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	129.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	30.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	6.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	3.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	93.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	3.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	3.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	7.000

**Call Order: 004 Proposal: T4477**

ALT	Item	Description	Unit	Quantity
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	19.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	24.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	24.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	28.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	627.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (23025665201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (23025665202)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (23025675201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,764.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,027.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	947.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.912
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	53.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	112.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	529.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.122
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,854.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.607
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	43.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	43.000
	0711- 14-241	THERMOPLASTIC, PREFORMED, YELLOW, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.141
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	34.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	101.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	9.488
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	2.163
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.878
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	5.178
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.944
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.911
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.379
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.905

**Call Order: 004 Proposal: T4477**

ALT	Item	Description	Unit	Quantity
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	2.219
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	2.219
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	26,198.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,931.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	291.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	131.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	60,208.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	43,879.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,052.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	21.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	3.000
	0715- 4- 24	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 45' MOUNTING HEIGHT	EA	96.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	6.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	8.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	121.000
<b>Section 0004 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	630.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	930.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	50.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	12.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	1.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	46.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	45.000
	0639- 2- 4	ELECTRICAL SERVICE WIRE, RELOCATE	LF	55.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	16.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	10.000

**Call Order: 004 Proposal: T4477**

ALT	Item	Description	Unit	Quantity
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	4.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	4.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	7.000
	0650- 1- 14	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	31.000
	0650- 1- 19	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	7.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	15.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	12.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	12.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	17.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
<b>Section 0005 Landscape / Peripheral</b>				
	0590- 70- 1	IRRIGATION SYSTEM REPAIRS (23025665201)	LS	1.000