



**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43206645201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43206645201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43206645201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.190
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	6,865.000
	0120- 1-	REGULAR EXCAVATION	CY	2,688.000
	0120- 6-	EMBANKMENT	CY	60.000
	0160- 4-	TYPE B STABILIZATION	SY	4,745.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	54.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	4,745.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	58,221.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	369.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	3,311.600
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	7.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	9.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	6.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	3.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	29.000
	0425- 6-	VALVE BOXES, ADJUST	EA	26.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	5.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	1,497.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	8.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	20.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	20.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	12.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	6,858.000
	0520- 1- 11	CONCRETE CURB & GUTTER, VARIABLE HEIGHT TYPE F	LF	12.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	190.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	90.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	64.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	566.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,310.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,667.000
	0522- 4-	BUS SHELTER PAD- CONCRETE	SY	60.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	1,286.000

**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	117.000
	0527- 2-	DETECTABLE WARNINGS	SF	534.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,755.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.581
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.387
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,198.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	619.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.111
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.309
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	76.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.891
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	21.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.089
	0751- 35- 13	ARCHITECTURAL, BUS SHELTER, F&I, 101-150 SF	EA	1.000
	0751- 35- 43	ARCHITECTURAL, BUS SHELTER, RELOCATE, 101-150 SF	EA	2.000
	0751- 36- 12	BICYCLE RACK, FURNISH & INSTALL, 2-6 BICYCLES	EA	4.000
	0751- 37-	TRASH RECEPTACLE	EA	4.000
	0999- 16-	PARTNERING, DO NOT BID (43206645201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43206645201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43206645202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43206645203)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	19.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	3.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	22.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	10.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	7.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	12.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	511.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43206645201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,198.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	619.000

**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.309
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	76.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	21.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.089
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,750.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	43.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	43.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.601
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.387
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.111
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.891
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	892.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,647.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	30.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	9,537.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	6,966.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	12.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	2.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	3.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	7.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	14.000
<b>Section 0004 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,185.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	840.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	39.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-410	ELECTRICAL POWER SERVICE, REL OVERHEAD	AS	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	10.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	4.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000

**Call Order: 014 Proposal: T4478**

ALT	Item	Description	Unit	Quantity
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	6.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	3.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	5.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	0660- 4- 51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	2.000
	0660- 4- 52	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY ABOVE GROUND EQUIPMENT	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	22.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	18.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	3.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
<b>Section 0005 Landscape / Peripheral</b>				
	0580- 2- 5	LANDSCAPE- RELOCATE TREE, TREES >5" CALIPER (43206645201)	EA	10.000
	0580- 2- 8	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK SABAL PALM ONLY (43206645201)	EA	3.000