

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180523	Call Order: 015	Proposal: T4482	District:04
Counties:	PALM BEACH			
Road Name:	SR 708 (W BLUE HERON BLVD) AND SR 809 (N MILITARY TRAIL)			
Limits:	VARIOUS INTERSECTIONS FROM SHILOH DR TO BURNS RD			
Project(s):	44007915201(*)	Federal Aid No:	D418013B	
Project(s):	44008015201	Federal Aid No:	D418014B	
Total Roadway Length:	6.483 Miles	Contract Days:	253	
Total Bridge Length:	0.047 Miles	Letting Date:	05/23/18	
Total Proposal Length:	6.483 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Calendar Days	
Proposal Budget Estimate:	\$531,304.00			

Please read the full advertisement

Description:

The improvements under this contract consist of lighting retrofit for three intersections along SR 708 (W. Blue Heron Blvd.) and eleven intersections along SR 809 (N. Military Trail).

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 015 Proposal: T4482

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44007915201)	LS	1.000
	0101- 1-	MOBILIZATION (44008015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44007915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44008015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,175.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,978.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	777.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	253.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	253.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	205.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	148.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44007915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44008015201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,645.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	41.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	14,463.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	13.000
	0715- 4- 23	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT	EA	3.000
	0715- 4- 31	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 30' MOUNTING HEIGHT	EA	2.000
	0715- 4- 32	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, INDEX 17515/715-002 FOUNDATION, 35' MOUNTING HEIGHT	EA	4.000
	0715- 4- 41	LIGHT POLE COMPLETE, FURNISH & INSTALL UTILITY CONFLICT POLE, SPECIAL FOUNDATION, 30' MOUNTING HEIGHT	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	8.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	30.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	23.000