

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT180523	Call Order: 017	Proposal: T4484	District:04
Counties:	BROWARD			
Road Name:	PETERS RD			
Limits:	FROM PINE ISLAND RD TO SR 817 (UNIVERSITY DR)			
Project(s):	43169815201(*)	Federal Aid No: D417061B		
Project(s):	43169815202	Federal Aid No: D417061B		
Total Roadway Length:	0.779 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	05/23/18	
Total Proposal Length:	0.779 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Calendar Days	
Proposal Budget Estimate:	\$1,536,151.00			

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, widening for the addition of bicycle lanes, patterned pavement in bicycle lanes, sidewalk and detectable warnings, drainage, signing and pavement markings, pedestrian signals, and lighting retrofit along Peters Rd.

Call Order: 017 Proposal: T4484

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43169815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43169815201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	9.400
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	116.000
	0102- 60-	WORK ZONE SIGN	ED	16,329.000
	0102- 71- 14	TEMPORARY BARRIER, F&I, TYPE K	LF	1,013.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	51,570.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	486.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	5,740.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	360.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	1,200.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,164.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-911- 1	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, SKIP	LF	2,073.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	960.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	2,073.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,863.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	26.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43169815201)	LS	1.000

Call Order: 017 Proposal: T4484

ALT	Item	Description	Unit	Quantity
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43169815202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43169815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,642.000
	0120- 1-	REGULAR EXCAVATION	CY	2,083.300
	0120- 6-	EMBANKMENT	CY	39.700
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	11.200
	0160- 4-	TYPE B STABILIZATION	SY	4,952.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	3,873.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	32,948.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	308.200
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2,120.300
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	2.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	3.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	10.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	103.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	10.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	12.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,017.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	7.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	223.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	760.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	780.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	121.000
	0527- 2-	DETECTABLE WARNINGS	SF	191.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,954.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.475
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.475
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43169815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43169815202)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	28.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	9.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	5.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	211.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43169815201)	LS	1.000

Call Order: 017 Proposal: T4484

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	918.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	699.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	342.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.066
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	71.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	68.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.220
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	15.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	15.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.370
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.065
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.321
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.079
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.380
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	15.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	165.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	12.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	2.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	2.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	2.000