

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT181114 Call Order: 001 Proposal: T3617 District:03

Counties: ESCAMBIA

Road Name: HANKS RD

Limits: OVER BREASTWORKS CREEK, FROM COUNTY MP 1.289 TO COUNTY MP 1.514

Project(s): 43228615201(*)

Federal Aid No: D318023B

Total Roadway Length: 0.214 Miles Contract Days: 290

Total Bridge Length: 0.011 Miles Letting Date: 11/14/18

Total Proposal Length: 0.225 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 15 Day Standard

Proposal Budget Estimate: \$1,392,956.00

Please read the full advertisement

Description:

The improvements under this contract consist of the construction of Bridge No. 484269 on Hanks Road over Breastworks Creek, removal of existing Bridge No. 484020, reconstruction of paved roadway approaches, surcharge embankment, an offsite detour, and other incidental construction on Hanks Road in Escambia County from County MP 1.289 to County MP 1.514.

Call Order: 001 Proposal: T3617

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43228615201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	59.800
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	90.400
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	57.800
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	225.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	2.100
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	15,245.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	7,224.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	17,752.000
	0450- 1- 1	PRESTRESSED BEAMS, TYPE II	LF	293.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	354.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	160.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	76.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	247.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	19.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,867.000
	0530- 74-	BEDDING STONE	TN	664.900
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43228615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43228615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	15,080.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,960.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,740.000

Call Order: 001 Proposal: T3617

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	2,210.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	97.000
	0110- 1- 1	CLEARING & GRUBBING (43228615201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	651.000
	0120- 4-	SUBSOIL EXCAVATION	CY	774.000
	0120- 6-	EMBANKMENT	CY	6,177.000
	0120- 74-	SURCHARGE EMBANKMENT	CY	3,056.000
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	4.000
	0145- 1-	GEOSYNTHETIC REINFORCED SOIL SLOPE	SF	5,221.000
	0160- 4-	TYPE B STABILIZATION	SY	4,512.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	5,331.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	3,310.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	352.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	17.500
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	531.000
	0536- 8- 12	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,331.000
	0571- 1- 13	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 3	SY	2,352.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43228615201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.350
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.350
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024