

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT181114 Call Order: 002 Proposal: T3619 District:03
 Counties: HOLMES
 Road Name: VALEE RD
 Limits: OVER BLUE CREEK, EXISTING BR NO. 524107
 Project(s): 43390215201(*) Federal Aid No: D318027B
 Total Roadway Length: 0.099 Miles Contract Days: 175
 Total Bridge Length: 0.017 Miles Letting Date: 11/14/18
 Total Proposal Length: 0.116 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Day Stndrd. Aquis

Proposal Budget Estimate: \$1,484,508.00

Please read the full advertisement

Description:

The improvements under this contract consist of base work, drainage improvements, signing and pavement marking, guardrail, replace existing Bridge No. 524107, utility improvements and other incidental construction on Valee Road over Blue Creek (new Bridge No. 524200) in Holmes County from CMP 0.852 to CMP 0.968.

Call Order: 008 Proposal: T3619

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43390215201)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	51.600
	0400- 2- 47	CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	69.300
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	105.500
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	257.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	12,078.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	20,979.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	9,306.000
	0450- 8- 22	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 15", WIDTH 52-54"	LF	508.000
	0455- 35- 21	STEEL PILING, 20" DIA. PIPE	LF	1,361.000
	0455-144- 21	TEST PILES - STEEL, 20" DIA PIPE	LF	330.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I Poured joint with backer rod	LF	89.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	272.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	24.700
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	744.400
	0530- 74-	BEDDING STONE	TN	265.100
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43390215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43390215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,625.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,512.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	700.000

Call Order: 008 Proposal: T3619

ALT	Item	Description	Unit	Quantity
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	378.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,624.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	363.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0110- 1- 1	CLEARING & GRUBBING (43390215201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	836.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	4,011.000
	0160- 4-	TYPE B STABILIZATION	SY	2,040.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	2,441.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,414.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	201.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	11.200
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	121.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	4.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	149.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	115.700
	0530- 74-	BEDDING STONE	TN	49.900
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	169.000
	0536- 7- 4	SPECIAL GUARDRAIL POST- FRANGIBLE LEAVE-OUT FOR MOUNTING THROUGH CONCRETE SURFACE	EA	6.000
	0536- 8- 12	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	EA	4.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	2.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,441.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43390215201)	LS	1.000