

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 010 Proposal: T3696

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43551825201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43551825201 (120 DAYS))	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,496.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	156.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	268.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,398.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	19.000
	0107- 1-	LITTER REMOVAL	AC	34.740
	0107- 2-	MOWING	AC	14.540
	0110- 1- 1	CLEARING & GRUBBING (43551825201 (2.00 AC))	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	372.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	8.000
	0120- 1-	REGULAR EXCAVATION	CY	1,032.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	193.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	4,540.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	10.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT	TN	5.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	40.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	86.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	36.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	129.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	70.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	58.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	481.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	5,469.000
	0527- 2-	DETECTABLE WARNINGS	SF	579.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,577.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43551825201)	LS	1.000
Section 0002 Signage				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	8.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,117.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	64.000