

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT181031 Call Order: 004 Proposal: T2715 District:02
Counties: SUWANNEE
Road Name: SR 10 (US 90)
Limits: FROM MADISON CO LINE TO CR 49
Project(s): 43429615201(*) Federal Aid No: D218021B
Total Roadway Length: 13.680 Miles Contract Days: 325
Total Bridge Length: 0.000 Miles Letting Date: 10/31/18
Total Proposal Length: 15.036 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Days Acquis.
Proposal Budget Estimate: \$9,472,228.00

Please read the full advertisement

Description:

Railroad insurance is required for this Proposal at time of contract execution. Please see the Specifications Package for more information.

The improvements under this contract consist of milling and resurfacing, base work, drainage improvements, shoulder treatment, curb and gutter, traffic signals, highway signing, guardrail, sidewalks/bicycle path and other incidental construction on SR 10/US 90 in Suwannee County from Madison County line to CR 49.

Call Order: 004 Proposal: T2715

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43429615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43429615201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43429615201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (43429615201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (43429615201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (43429615201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (43429615201)	LS	1.000
	0102- 2- 6	SPECIAL DETOUR 6 (43429615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	224.000
	0102- 60-	WORK ZONE SIGN	ED	71,970.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	3,272.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	2,784.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	361,840.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	397.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	9,641.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,130.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,300.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,300.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	265.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	670.000

Call Order: 004 Proposal: T2715

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	14,444.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	30.000
	0107- 1-	LITTER REMOVAL	AC	2,556.810
	0107- 2-	MOWING	AC	2,285.790
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43429615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43429615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	9,327.000
	0120- 1-	REGULAR EXCAVATION	CY	1,586.000
	0120- 4-	SUBSOIL EXCAVATION	CY	11,420.000
	0120- 6-	EMBANKMENT	CY	13,255.000
	0160- 4-	TYPE B STABILIZATION	SY	20,272.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	11,828.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	11,505.000
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	21,736.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	191,409.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	12,619.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	71,800.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	19,497.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	25,868.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	8.800
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	2.300
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	2.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	9.000
	0425- 6-	VALVE BOXES, ADJUST	EA	8.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	315.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	16.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	12.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	31.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	10.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	254.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	760.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	201.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,077.000
	0527- 2-	DETECTABLE WARNINGS	SF	499.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	107.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	215.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	66,958.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	31.634
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,927.000

Call Order: 004 Proposal: T2715

ALT	Item	Description	Unit	Quantity
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,695.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.070
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	19.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	76.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	27.594
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	63.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	3.483
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.090
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43429615201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	27.888
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	69.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	50.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	5.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43429615201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	870.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,695.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.714
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	19.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	76.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	47.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,468.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.221
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	33.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	1,927.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	641.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	70.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	70.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	27.604
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.373
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	23.894

Call Order: 004 Proposal: T2715

ALT	Item	Description	Unit	Quantity
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.009
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.483
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,620.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,016.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	120.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	46.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	4.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	4.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	575.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	525.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	4.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	3.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	9.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	22.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	10.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	32.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	14.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	24.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	21.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	16.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	14.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	4.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	4.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	19.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	20.000

Call Order: 004 Proposal: T2715

ALT	Item	Description	Unit	Quantity
	0700- 11-391	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, BLANK OUT SIGN, UP TO 12 SF	AS	5.000
	0700- 11-700	ELECTRONIC DISPLAY SIGN, REMOVE- OVERHEAD MOUNT	AS	5.000