

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT181031 Call Order: 006 Proposal: T2720 District:02

Counties: ALACHUA

Road Name: SR 26 (NEWBERRY RD)

Limits: FROM 75TH ST TO NW 69TH TERRACE

Project(s): 43735415201(\*) Federal Aid No: D218007B

Total Roadway Length:	0.568 Miles	Contract Days:	200
Total Bridge Length:	0.000 Miles	Letting Date:	10/31/18
Total Proposal Length:	0.568 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120 Days

Proposal Budget Estimate: \$2,395,497.00

Please read the full advertisement

Description:

GRU Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T1000-9.

Please upload completed Table A as a zip file within your EBS File using the "File Attachment Upload" tab before submitting your bid.

The improvements under this contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb and gutter, traffic signals, lighting, highway signing, guardrail, sidewalk, pier protection barrier wall and other incidental construction on SR 26 (Newberry Rd) from 75th St to NW 69th Terrace in Alachua County.

**Call Order: 006 Proposal: T2720**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43735415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43735415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	80.000
	0102- 60-	WORK ZONE SIGN	ED	7,790.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	350.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	285.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,000.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	164.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	78.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	598.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	800.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	800.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,416.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	21.000
	0107- 1-	LITTER REMOVAL	AC	47.720
	0107- 2-	MOWING	AC	29.900
	0110- 1- 1	CLEARING & GRUBBING (43735415201)	LS	1.000

**Call Order: 006 Proposal: T2720**

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,071.000
	0120- 1-	REGULAR EXCAVATION	CY	1,952.000
	0120- 4-	SUBSOIL EXCAVATION	CY	995.000
	0120- 6-	EMBANKMENT	CY	1,701.000
	0160- 4-	TYPE B STABILIZATION	SY	3,994.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	584.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,385.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	851.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	17,083.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	4,323.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	560.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,505.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	3.900
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	1.600
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	2.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	4.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 3- 43	JUNCTION BOX, DRAINAGE, P-7, PARTIAL	EA	3.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	138.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	146.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,346.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	46.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	325.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	423.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	308.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	253.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	269.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	15.000
	0527- 2-	DETECTABLE WARNINGS	SF	123.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	203.000
	0536- 1- 12	GUARDRAIL, ROADWAY, MODIFIED THRIE BEAM-DOUBLE FACE	LF	31.000
	0536- 7- 4	SPECIAL GUARDRAIL POST- FRANGIBLE LEAVE-OUT FOR MOUNTING THROUGH CONCRETE SURFACE	EA	19.000
	0536- 8- 13	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	659.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0544- 75- 1	CRASH CUSHION	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	3,859.000

**Call Order: 006 Proposal: T2720**

ALT	Item	Description	Unit	Quantity
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,439.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.965
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.322
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.228
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.473
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43735415201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	7.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43735415201)	LS	1.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
<b>Section 0003 Lighting</b>				
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	12.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	12.000
<b>Section 0004 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	112.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	229.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	4.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	2.000
	0649- 26- 7	STEEL MAST ARM ASSEMBLY, REMOVE, REMOVE ARM AND ATTACHMENTS; POLE REMAINS	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	23.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	10.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	25.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0653- 1- 40	PEDESTRIAN SIGNAL, RELOCATE	AS	4.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	6.000
	0660- 4- 51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000
	0660- 4- 60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	1.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	5.000

Call Order: 006 Proposal: T2720

ALT	Item	Description	Unit	Quantity
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0682- 1-400	ITS CCTV CAMERA, RELOCATE	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
<b>Section 0005 Utilities</b>				
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (43735415201)	LS	1.000