

Call Order: 001 Proposal: T3617

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	2,210.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	97.000
	0110- 1- 1	CLEARING & GRUBBING (43228615201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	651.000
	0120- 4-	SUBSOIL EXCAVATION	CY	774.000
	0120- 6-	EMBANKMENT	CY	6,177.000
	0120- 74-	SURCHARGE EMBANKMENT	CY	3,056.000
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	4.000
	0145- 1-	GEOSYNTHETIC REINFORCED SOIL SLOPE	SF	5,221.000
	0160- 4-	TYPE B STABILIZATION	SY	4,512.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	5,331.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	3,310.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	352.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	17.500
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	531.000
	0536- 8- 12	APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0536- 85- 25	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,331.000
	0571- 1- 13	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 3	SY	2,352.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43228615201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.350
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.350
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024