

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT181031	Call Order: 009	Proposal: T3680	District:03
Counties:	WALTON			
Road Name:	SR 30 (US 98)			
Limits:	AT JD MILLER RD INTERSECTION			
Project(s):	43815515201(*)	Federal Aid No: D318064B		
Total Roadway Length:	0.132 Miles	Contract Days:	45	
Total Bridge Length:	0.000 Miles	Letting Date:	10/31/18	
Total Proposal Length:	0.132 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Day Stndrd Aquis	

Proposal Budget Estimate: \$165,895.00

Please read the full advertisement

Description:

The Contract Bond requirement will be waived if the bid is such that the contract price will be \$250,000 or less.

The improvements under this contract consist of construction of a westbound right turn lane with signing and pavement markings on S.R. 30 (US 98) at JD Miller Road intersection in Walton County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 009 Proposal: T3680

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43815515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43815515201 (45 DAYS))	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	720.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,693.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	45.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	59.000
	0104- 10- 3	SEDIMENT BARRIER	LF	842.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	6.800
	0107- 2-	MOWING	AC	5.320
	0110- 1- 1	CLEARING & GRUBBING (43815515201 (0.58 AC))	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	290.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	238.000
	0160- 4-	TYPE B STABILIZATION	SY	1,249.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	1,614.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	306.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	925.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	382.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	32.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	241.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	34.800
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,632.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43815515201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43815515201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	75.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	35.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.057
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.127
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.091
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.008