

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT180926 Call Order: 003 Proposal: T1734 District:01
 Counties: CHARLOTTE
 Road Name: SR 45 (US 41)
 Limits: FROM S OF RIO VILLA DR TO AIRPORT RD
 Project(s): 43498815201(*) Federal Aid No: D118082B
 Total Roadway Length: 0.937 Miles Contract Days: 130
 Total Bridge Length: 0.000 Miles Letting Date: 09/26/18
 Total Proposal Length: 0.937 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Days (Aqui Time)

Proposal Budget Estimate: \$717,934.00

Please read the full advertisement

Description:

The improvements under this contract consist of installation of highway lighting on State Road 45 (U.S. 41) from south of Rio Villa Drive northerly 0.937 miles to Airport Road in the City of Punta Gorda, Charlotte County.

Call Order: 003 Proposal: T1734

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43498815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43498815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,250.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,320.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,225.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (43498815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43498815201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,205.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,830.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	46.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	27,745.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	90.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	605.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	41.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	14.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	41.000